

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21796-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 22-11S-22W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SPALSBURY Well #: 1  
County: TREGO Total Vertical Depth: 3990 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3980	0	w/425 sxs cmt
SURF	8.625	261	0	w/160 sxs cmt

#129.68

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2007 9:30 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: DICK SCHRAMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Stage collar at 2568' w/575 sxs. CIBP at 3800'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2007 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Copeland rigged to 4 1/2" casing with a swedge and valve - pumped 50 sxs 60/40 pozmix, followed with 120 sxs with 300# hulls mixed in.  
Max. P.S.I. 800#. S.I.P. 350#.  
Dug out 8 5/8" braden head - rigged to backside - pumped 35 sxs with 50# hulls mixed in.  
Max. P.S.I. 100#. S.I.P. 0#.  
Blew hole in top of braden head. Backside standing full.

Perfs:

Top	Bot	Thru	Comments
3915	3925		

**INVOICED**  
DATE 5-15-07  
INV. NO. 2007061748

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 14 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING & ACID-TICKET #C031771.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

MAY 11 2007


PT

replacement card  
 STRATA ENERGY RESOURCES CORPORATION  
 NEWPORT BEACH, CA. 92660

22-11 -22W  
 NW NE SE

#1 SPALSBURY

site: 3 N & 6-3/4 E OF WAKEENEY, KS      city: TREGO      API 15-195-21796  
 contr: RED TIGER DRILLING      field: GAGELMAN SO. EXT (1/8  
 geol: ROBERT WILSON      S)  
 fr      spd      drig      card      last  
 date 10/17/85      date 11/02/85      comp 11/08/85      issued 08/07/86      revised 06/03/87



ELV: 2307 KB LOG	
tops .....	depth/datum
ANH.....	1764 +543
B/ANH.....	1811 +496
TOP.....	3342 -1035
HEEB.....	3554 -1247
TOR.....	3575 -1268
LANS .....	3591 -1284
BKC.....	3829 -1522
MARM .....	3902 -1595
CONG.....	3944 -1637
RTD.....	3990 -1683

**IP status:**  
**OIL, P 30 BO & 5 BWP, MARM 3915-3925 ,**  
 CSG: 8-5/8" 261 / 160 SX, 4-1/2" 3980 / 425 SX, MULTI  
 STAGE COLLAR AT 2568 / 575 SX  
 NO CORES  
 DST (1) 3910-3930 (MARM), / 30-45-45-45, REC 100' MCO  
 ISIP 1218# FSIP 1185# IFP 55# -66# FFP 77# -77# IHP  
 2155# FHP 2134# BHT 111 "  
 MICT - CO, PF (MARM) 3915-3925, W / 2 SPF, AC 1500  
 GAL, GSO, SET 2-3/8" TBG (DEPTH NA), POP, P 30 BO & 5  
 BWP (GR 38), 1/5/86  
 INFO RELEASED: 6/3/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

*051 - 211' - 11000*