

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03102-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 11-14S-20W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BEFORT Well #: 2
County: ELLIS Total Vertical Depth: 3862 feet

Operator License No.: 4871
Op Name: HITSCHMANN, CURTIS LEE DBA CURT
Address: 742 N HWY 281
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3853	0	100 SX
SURF	8.625	232	0	150 SX

\$ 125.52

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2007 3:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CURT'S OIL OPERATIONS Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 600# hulls.
Squeezed at 1141' w/60 sxs-1974; 1038' w/250 sxs-1975; 2868' w/250 sxs-1975.
Poor casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2007 6:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

D.S.& W. RIH with tubing to 2100'. Copeland rigged to tubing - pumped 180 sxs 60/40 pozmix with 450# hulls mixed in.
Pulled tubing to 1200'. Copeland rigged to tubing - pumped 120 sxs 60/40 pozmix with 150# hulls mixed in to circulate cement to pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 25 sxs 60/40 pozmix.
Max. P.S.I. 300#. S.I.P. 250#.
8 5/8" - pulled bull plug off - backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3825	3830		
3556	3560		
3540	3543		

INVOICED

DATE 5-15-07

INV. NO. 2007061749

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COPELAND & ACID CEMENTING COMPANY-TICKET C-031770.

MAY 14 2007

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed [Signature]

(TECHNICIAN)


MAY 10 2007

PKT

B E ASH #2 BEFORT 11-14-20W
 SE NW NE
 Contr. BEA DRLG CO ELLIS County
 E 2227RB Comm. Comp. 10-16-59 IP 25 BOPD

Tops	Depth	Datum
ANH	1510	+717
LANS	3508	-1281
1st GORH	3824	-1597
CONG	3830	-1603
2ND GORH	3850	-1623
TD	3862	-1635

Casing
 8" 232
 5" 3854
 DST 3830-62/1 HR, 1170' o, 120'
 FR 0, BHP 1145#
 CO 3862



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS