

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04565-00-01  
Spot: NWSESW Sec/Twnshp/Rge: 28-19S-11W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SCHWAMBORN Well #: 9  
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 5920  
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G  
Address: PO BOX 522  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3366	0	w/120 sxs cmt
SURF	8.625	311	0	w/185 sxs cmt

\$ 109.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2007 10:00 AM  
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: Ordered 315 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Junk in hole - casing leaks.  
Drilled to 888.40' - spotted 100 gallons 20% acid on 05/04/2007.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2007 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Cyclone Well Service RIH with tubing to 888'.  
Allied rigged to tubing - pumped 200 sxs 60/40 pozmix neat, followed with 40 sxs with 100# hulls mixed in.  
Pulled tubing - tried to break off head - parted 5 1/2" casing.  
Allied rigged to 8 5/8" - pumped 60 sxs 60/40 pozmix to circulate cement up 5 1/2" casing.  
POOH. Hole standing full.  
Max. P.S.I. 150#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3065	3134	OH	

**INVOICED**  
DATE 5-15-07  
INV. NO. 2007061752

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 14 2007

Remarks: ALLIED CEMENTING COMPANY-TICKET #30383.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

(TECHNICIAN)

MAY 11 2007

EL DORADO REFINING CO

28-19S-11W  
NW SE SW

#9 SCHWAMBORN OWWO

site: 1/4 N & 3/4 E OF ELLINWOOD K/S  
contr: UNKNOWN

city: BARTON  
field: ANTON

API 15-009-04565

ged:	spc	drig	card	last
fr	date	comp	issued	revised
date	06/21/1962	06/27/1962	02/19/2001	02/19/2001


ELV: 1782 DF LOG	
tops.....	depth/datum
ANH.....	945 +837
B/ANH.....	970 +812
HEEB.....	2916 -1134
TOR.....	2935 -1153
DOUG.....	2947 -1165
BR LM.....	3036 -1254
LANS.....	3055 -1273
CONG.....	3318 -1536
ARB.....	3327 -1545
LTD OLD.....	3367 -1585
RTD OLD.....	3370 -1588

**IP status:**  
**OIL, LKC 3065-3134 OA, 06/28/1962**  
**OLD INFO:** OPERATOR WAS EL DORADO REFINING CO, 9  
 SCHWAMBORN, SPD 02/20/1956, 03/01/1956 8-5/8" 311 / 185  
 SX, 5-1/2" 3366 / 120 SX, OIL, P 26 BOPD, NW, LKC  
 3065-3086 OA, 03/23/1956(CARD ISSUED 03/30/1956)  
 CONTR: PRIME DRILLING  
 COMMENT: WAS TEMP AP I OG-9501  
 DRLR SD ZNS: 0-95, 311-550 (SH, SD & RED BED)  
 NO CORES  
 DST (1) 3053-3076 (LANS), / 60-20-0-0, GTS/29", TSTM, REC  
 180' OIL & GCM, W/TR SFO, REMARK: FP NA ISIP 740#

COPYRIGHT 2001  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

EL DORADO REFINING CO

28-19S-11W  
NW SE SW

#9 SCHWAMBORN OWWO

DST (2) 3114-3132 (LANS), / 30-20-0-0, GTS/9", TSTM, REC 90' HO & GCM, REMARK: FP NA ISIP 70#  
 DST (3) 3185-3205 (LKC), / 45-20-0-0, REC 15' M, REMARK: FP NA ISIP 0#  
 DST (4) 3327-3338 (ARB), / 45-20-0-0, REC 10' M, REMARK: FP NA ISIP 0#  
 MICT - CO, PF (ARB) 24/3330-3334, NS, NAT, SET PLUG AT 3100, PF (LKC) 24/3065-3071, NS, NAT, AC  
 1000 GAL (15%), SWB LD, SO, PF (LKC) 24/3082-3086, AC 2500 GAL (15%), SWB LD, KOF 2-1/2 BOPH,  
 RE-AC 1500 GAL (15%), SWB LD, KOF 16-1/2 BO/8 HRS, POP, IPP 26 BOPD, NW, 3/23/1956  
**NEW INFO:** FR 06/21/1962, REWORKED 06/27/1962 DC 06/27/1962 MICT - CO TO 3300, SET CIBP AT  
 3298, W/5 SX CMT ON TOP, PF (LKC) 3129-3134, W / 4 SPF, AC'D, SO, POP, OIL WELL (POTENTIAL  
 NOT RPTD), RESUMED PROD 6/28/1962, COMMINGLED W/OLD PAY (LKC 3065-3086 OA)