

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202 RECEIVED
 KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-09300623-00-00
 LEASE NAME Livengood

APR 11 2007

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
1980 Ft. from N Section Line
1980-200 Ft. from E Section Line
 SEC. 26 TWP. 22S RGE. 36W (E) or (W)

CONSERVATION DIVISION
 WICHITA, KS

LEASE OPERATOR Devon Energy Production Company, L.P.
 ADDRESS 20 N Broadway Ste 1500 Oklahoma City, OK. 73102
 PHONE/(405) 552-4515 OPERATORS LICENSE NO. 32606

COUNTY Kearny
 Date Well Completed 6-24-52
 Plugging Commenced 8-24-06
 Plugging Completed 8-25-06

Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-23-06 (date)
 by Ken Jehlik (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Herington Krider Winfield Depth to Top 2622 Bottom 2700 T.O. 2700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	258	0
				7	2590	680

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Set CIBP 2250 with 4 sacks cement on top 2230, pulled 7" casing at 680 feet, ran tubing to 882, pumped 125 sacks cement, tagged at 598, pumped 100 sacks cement at 290 feet, top at 80 feet, pumped 40 sacks cement 60 feet to surface, pulled tubing, dug out, welded on steel ID plate

Name of Plugging Contractor H&K Plugging & Salvage License No. 31705

Address P.O. Box 2742 Pampa, Texas 79066-2742

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Devon Energy

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Ron Fields

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ronald D. Fields

(Address) Box 918, Canadian, TX 79014

SUBSCRIBED AND SWORN TO before me this 5th day of April, 2007

Joseph Rutelous
 Notary Public

My Commission Expires: 2-3-10

USE ONLY ONE SIDE OF EACH FORM

PEI