

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cimarex Energy, Co.
 Address: RR. 1 Box 83 Satanta, KS 67870
 Phone: (620) 276-3693 ext. 13 Operator License #: 33094
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 11/06/06 (Date)
 by: Ken Jehlik (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Herrington Depth to Top: 2530 Bottom: 2534 T.D. _____
Krider Depth to Top: 2562 Bottom: 2582 T.D. _____
Winfield Depth to Top: 2609 Bottom: 2611 T.D. 2613

API Number: 15-055-00312-0000
 Lease Name: Johnson
 Well Number: 1
 Spot Location (QQQQ): C - SE/4 - _____
1320' Feet from North / South Section Line
1320' Feet from East / West Section Line
 Sec. 9 Twp. 22 S. R. 34 East West
 County: Finney
 Date Well Completed: 06/20/57
 Plugging Commenced: 03/20/07
 Plugging Completed: 03/22/07

KCC PER
Per 2/23/07
4/23/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Top of Permian	Water 1050	0	291	8 5/8"	291	0
Chase	Gas 2500-TD	0	2613	5 1/2"	2613	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

07/28/06 set CIBP @ 2467'. 03/20/07 set CIBP @ 1100'. Test to 580 PSIG. Pump 60 sx Class A cmt into holes 885-1073'. TOC 994'.
 Pumped 60 sx Class A dn Tbg, pump 1 bbl water, pull tbg, pump 50 sx Class A cmt. Circ @ surf. Pump 113 sx
 Class A cmt dn 8 5/8" x 5 1/2" annulus. Press to 500 psig. Top off 5 1/2" w/ 13 sx Class A. Cutoff 5 1/2" & 8 5/8" 4' below GL.

Name of Plugging Contractor: Eagle Well Service License #: 7407 **RECEIVED KANSAS CORPORATION COMMISSION**
 Address: Liberal, KS **APR 18 2007**

Name of Party Responsible for Plugging Fees: Cimarex Energy, Co. **CONSERVATION DIVISION WICHITA, KS**
 State of Kansas County, Haskell, ss.

Kent Pendergraft (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kent Pendergraft
 (Address) Rt 1 Box 83, Satanta, KS 67870

MELISSA IMLER
 Notary Public - State of Kansas
 My Appt. Expires 11-17-2010

SUBSCRIBED and SWORN TO before me this 17 day of April, 2007
Melissa Imbler My Commission Expires: 11-17-2010
 Notary Public

AKG