

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

23141

API NUMBER 163-21141-00-00

LEASE NAME Stucky

WELL NUMBER B #3

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 30 TWP. 9 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 6/3/91

Plugging Commenced 4/7/95

Plugging Completed 4/7/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd Street North, Bldg. 300
Wichita, KS 67226

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/7/95 (date)

by Herb Dienes (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arb, LKC, Topeka Depth to Top 3276 Bottom 3618 T.D. 3670

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	211	0
				5-1/2	3665	0
						5/9/95

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Bottom hole sanded in from casing break in at 1200. Spotted 25" sx 60/40 Poz at 1400 through tubing. Pumped 225 sx 60/40 Poz with 400# hulls down casing. Pressured to 600 psig. Shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address Route 1, Box 183-B, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.


W.R. Horigan

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) WR Horigan

(Address) 8100 E. 22nd Street North, Bldg. 300 Wichita, KS. 67226

SUBSCRIBED AND SWORN TO before me this 8th day of May, 19 95



My Commission Expires: April 15, 1998

Julie I. McGuire
Notary Public