

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Timberline Oil & Gas Corporation
Address: 4000 Penrose Lane, Rapid City, S.D. 57702
Phone: (605) 341-3400 Operator License #: 9232

API Number: 15-151-21712-00-00
Lease Name: Lemon
Well Number: 4

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (OOQQ): _____ SE . NW . SW
1650 Feet from _____ North / South Section Line
4290 Feet from East / _____ West Section Line
Sec. 33 Twp. 26 S. R. 13 _____ East West

The plugging proposal was approved on: _____ (Date)
by: Steve Pfiefer (KCC District Agent's Name)

County: Pratt
Date Well Completed: _____
Plugging Commenced: 3-22-07
Plugging Completed: 3-27-07

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	321'	None
				5-1/2"	4536'	3039'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3770' and 5 sxs. cement. Cut casing loose @3039', pulled up to 850', pumped 15 sxs. gel & 50 sxs. cement, no circulation. Pumped 80 sxs. cement @350', no circulation. Top of cement @486', ran 360' of 2-3/8" tubing, pumped 80 sxs. cement & 100# hulls. Top of cement @389', ran tubing back in, pumped 50 sx. cement and 100# hulls, pulled up to 60', pumped 80 sxs. cement. Topped off with 5 sx. cement 60/40 pos, 6% gel.
Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Timberline Oil & Gas Corporation

APR 19 2007

State of Kansas County, Rice ss.

CONSERVATION DIVISION

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of April, 2007

Irene Herzberg
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT