

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: P.O Box 399, Garden City Ks. 67846
Phone: (620) 272 - 1023 Operator License #: 4058
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 4/11/07 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing/KC Depth to Top: 3779' Bottom: 3802' T.D. 3840'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-21169 -00-00
Lease Name: Gollison Collision *KCC PRT*
Well Number: #6 *PERCP2/3*
Spot Location (QQQQ): C - SW - NW - SW
1650' Feet from North / South Section Line
4950' Feet from East / West Section Line
Sec. 35 Twp. 9S S. R. 22W East West
County: Graham *KCC PRT*
Date Well Completed: 9/25/79 1/9/80 4/19/07
Plugging Commenced: 4/11/07 *per RBD*
Plugging Completed: 4/11/07

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|-------------|--|-------|------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Lansing | oil and gas | Surface | 250' | 85/8 | 250' | 0 |
| | | Surface | 3836' | 51/2 | 3836' | 0 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Perf 1850' and 1125'. Ran tbg to 2060'. Swift hooked up to tbg and pumped 100 sx 60/40 pos 10% gel w/ 200# hulls. Pulled tbg to 1157'. Swift hooked up to tbg and pumped 200sx 60/40 pos 10% gel w/ 200# hulls. Pulled tbg tp 500', Swift hooked up to tbg and pumped 65sx 60/40 pos w/200# hulls, Cement circulated to surface. Pulled tbg. Swift hooked up to 51/2 casing and topped off w/10sx 60/40 pos 10% gel. Dug out 85/8 surface head. Had cement to surface.

Name of Plugging Contractor: Western Well Drilling, LLC *Swift Services inc* License #: 33669 *32382* RECEIVED
Address: P.O. box 466 Ness City Kansas 67560 APR 16 2007
Name of Party Responsible for Plugging Fees: American Warrior Inc. *KCC PRT 4/19/07*
State of Kansas County, Finney, ss. *per CP2/3* CONSERVATION DIVISION WICHITA, KS
Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]
(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 13 day of April, 20 07
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

per