

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEREXCO, INC.
Address: PO BOX 723 HAYS, KS 67601
Phone: (785) 628-6101 Operator License #: 5363
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-22-07 (Date)
by: CASE MORRIS (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

TOP	Depth to Top: <u>2767</u>	Bottom: <u>80</u>	T.D. _____
PLATT	Depth to Top: <u>2839</u>	Bottom: <u>46</u>	T.D. _____
TOR	Depth to Top: <u>2913</u>	Bottom: <u>19</u>	T.D. _____

API Number: 15-167-05736-0000
Lease Name: NWBU
Well Number: 1-1
Spot Location (QQQQ): S/2 - S/2 - SE - KCC
406 Feet from ☐ North / ☒ South Section Line SKT
1392 Feet from ☒ East / ☐ West Section Line SKT
Sec. 32 Twp. 15 S. R. 12 ☐ East ☒ West CP2/3
County: RUSSELL
Date Well Completed: 2-12-50 original
Plugging Commenced: 3-22-07
Plugging Completed: 3-27-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
TOP	OIL	0	3256	5 1/2	2-12-50	----
PLATT	OIL	0	349	8 5/8	2-12-50	----
TOR	OIL					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RUN TBG AND CATCHER PULL LOCKSET, RIG UP CSG JACK TOOK 200# TO MOVE CSG 600# MOVED CSG 3" SAND WELL BACK W/ 30 SKS OF FINE SAND. RIG UP PERF TECH RUN IN TAG SAND AT 1735
DUMP 5 SKS CMT ON SAND. FREE POINT CSG, CSG FREE AT 1550 W/ 900# ON JACK CUT CSG OFF AT 1550 PULL CSG TO 1415 RIG UP ALLIED CMT SPOT140 SKS 60/40 POS 10%GEL 200# HULLS
PULL CSG TO 774 SPOT 25 SKS 60/40 POS 10%GELL PULL CSG TO 647 TBG TONGS QUIT WORKING HUDR OIL BOILING OUT TANK. CIRC CMT OUT OF HOLE PULL 1 JT. RIG UP ALLIED CMT 647
SPOT 25 SKS 60/40POS 10% GEL PULL TO 422 MIX 120 SKS 60/40 POS 10% GEL 400# HULLS CIRC TO SURF. PULL REST OF CSG HAE A TOTAL OF 1547' TOP OFF 7" W/ 15 SKS 60/40 POS 10%GEL

Name of Plugging Contractor: BEREXCO, INC. License #: 5363
Address: PO BOX 723 HAYS, KS 67601
Name of Party Responsible for Plugging Fees: BEREXCO, INC. BOB GRANT
State of KS County, ELLIS, ss.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 11 2007

CONSERVATION DIVISION
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

SHANNA MILLER
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 8-17-09

(Signature) Robert Grant
(Address) PO BOX 723 HAYS, KS 67601

SUBSCRIBED and SWORN TO before me this 6 day of APRIL, 20 07

Shanna Miller
Notary Public

My Commission Expires: 8-17-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202