

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: BEREXCO, INC.

Address: PO BOX 723 HAYS, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: OIL Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3-21-07 (Date)

by: MARVIN MILLS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ARB Depth to Top: 3296 Bottom: 3301 T.D.

LKC Depth to Top: 3040 Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-009-15693-00-00

Lease Name: NWBU

Well Number: 8-8

Spot Location (QQQQ): NW - NE - SE - KCC PIET

2310 Feet from North / South Section Line 5/1607

990 Feet from East / West Section Line per RBDM

Sec. 6 Twp. 16 S. R. 12 East West CP213

County: BARTON

Date Well Completed: 1-4-51

Plugging Commenced: 3-21-07

Plugging Completed: 3-22-07

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include ARB and LKC formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

DIG OUT CELLER HAVE CMT FLOOR W/23" HOLE 7" CSG ON CLAMP 5-1/2 CSG ON CLAMP POOR BOY 7" TO 5-1/2 SET 30"X8' PIPE IN HOLE AND BACKFILL RIG UP PERFTECH SHOOT 2 HOLES AT 1475-810-150' RUN OPEN ENDED TBG TO 2642 RIG UP ALLIED CMT MIX 100SKS 60/40 10% GEL 300# HULLS PULL TO 1318 MIX 100 SKS 250# HULLS PULL TO 648 MIX 50 SKS 125# HULLS CIRC TO SURF. PULL TBG HOOK TO 5-1/2 MIX 65 SKS 25# HULLS MAX PRES 250# SHUT IN 100# HOOK TO 78" MIX 50 SKS MAX PRESS 400# SHUT IN 100# FILL 23" HOLE MIX 35 SKS FILL TO SURF


Name of Plugging Contractor: BEREXCO, INC. License #: 5363 RECEIVED

Address: PO BOX 723 HAYS, KS 67601 KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: BEREXCO, INC. BOB GRANT APR 1 1 2007

State of KS County, ELLIS, ss. CONSERVATION DIVISION WICHITA, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Robert Grant

(Address) PO BOX 723 HAYS, KS 67601

SUBSCRIBED and SWORN TO before me this 6 day of APRIL, 20 07

Shanna Miller My Commission Expires: 9-19-09 Notary Public