

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEREXCO, INC.

Address: PO BOX 723 HAYS, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3-28-07 (Date)

by: MARVIN MILLS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

PLATT Depth to Top: 2834 1/2 Bottom: 45 T.D. _____

LKC Depth to Top: 2991 Bottom: 3173 T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-03262-00-00

Lease Name: NWBU

Well Number: 9-2

Spot Location (QQQQ): NW - NW - SW -

2305 Feet from North / South Section Line

5031 Feet from East / West Section Line

Sec. 5 Twp. 16 S. R. 12 East West

County: BARTON

Date Well Completed: 8-1-48

Plugging Commenced: 3-28-07

Plugging Completed: 3-30-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
PLATT	OIL	0	3242	5 1/2	8-1-48	---
LKC	OIL	0	522	8 5/8	8-1-48	----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIG UP PERF TECH SHOT 2 HOLES AT 1450 AND 780. RUN TBG TO 2863. RIG UP ALLIED CEMENTING SPOT 50 SKS 60/40 POS 10% GEL 200# HULLS. PULL TO 1628 MIX 100 SKS 60/40 POS 10% GEL 200# HULLS CIRC TO SURF PULL TBG HOOK TO 5 1/2 MIX 120 SKS 60/40 POS 10% GEL CIRC CMT TO SURF ON 8 5/8 SHUT. 8 5/8 IN MIX 130 SKS 60/40 POS 10% GEL 100# HULLS. MAX PRESS 200# SHUT IN PRESS 200#

Name of Plugging Contractor: BEREXCO, INC License #: 5363 **RECEIVED** KANSAS CORPORATION COMMISSION

Address: PO BOX 723 HAYS, KS 67601 **APR 11 2007**


Name of Party Responsible for Plugging Fees: BEREXCO, INC. BOB GRANT CONSERVATION DIVISION

State of KS County, ELLIS, ss. **WICHITA, KS**

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Robert Grant

(Address) PO BOX 723 HAYS, KS 67601



SUBSCRIBED and SWORN TO before me this 6 day of APRIL, 20 07

Shanna Miller
Notary Public My Commission Expires: 9-19-09