

SIDE TWO

Operator Name AL-LA-LYN Oil, Inc. Lease Name Jackson Well # #1
 Sec. 28 Twp. 9S Rge. 20W East West
 County Rooks

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheets if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets.)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy.)

DST #2, 3807-3894 30"-30" -- 30"-30" 1st Open: Weak Blow 2nd Open: No Blow Rec'd: 45' Dtl. Mvd. IFP 96-96 ISIP 105 Psi FFP 96-96 FSIP 96 Psi HP 1940-1930 M&M Temp. 109°F	DST #1, 3886-3892 30"-30" -- 30"-30" 1st Open: Weak Blow, Dred 15" 2nd Open: No Blow, Flushed tool, No Blow. Rec'd 15' Mvd. Tool Plugged, Pressure invalid.
---	--

Formation Description

Log Sample

Name

FORMATION TOPS			
FORMATION	SAMPLE	E. LOG	DATUM
Anhydrite	1781	1782	+507
Base/Anh.	1821	1821	+468
Topeka	3320	3324	-1035
Heebner	3528	3531	-1242
Toronto	3549	3551	-1262
Lansing	3566	3569	-1280
BKC	3787	3791	-1502
Congl. Chert	3850	3848	-1559
Congl. Shale	3866	3864	-1575
Arbuckle	3888	3894	-1605
RTD	3920	3922	-1631

CASING RECORD

New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
surface	12 1/4	8 5/8	19#	208'	60/40poz	140	3%cc 2%gel

PERFORATION RECORD

Shots Per Foot Specify Footage of Each Interval Perforated

Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used) Depth

TUBING RECORD

Size Set At Packer At Liner Run Yes No

Date of First Production Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil Bbls. Gas Mcf Water Bbls. Gas-Oil Ratio Gravity

Disposition of Gas:

Vented Sold Used on Lease
 (If vented, submit ACO-18.)

METHOD OF COMPLETION

Open Hole Perforation Dually Completed Commingled
 Other (Specify) _____

Production Interval

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

ORIGINAL

Phone Plainville 913-434-2812
 Phone Ness City 913-798-3843

New
ALLIED CEMENTING CO., INC. No. 9626
 Home Office P. O. Box 31 Russell, Kansas 67665

Date	Sec.	Twp.	Range	Called Out	On Location	Job Start	Finish
12-18-90	28	9 ^s	20 ^w	2:00 A.M.	3:25 A.M.	5:00 A.M.	9:45 A.M.
Lease	Well No.	Location			County	State	
Jackson	1	Palco (Booster St.) 3/4N 3/4E			Rooks	Ks.	

Contractor <i>Halloway Drilling Co., Inc. Rig #1</i>	
Type Job <i>Plug</i>	
Hole Size <i>7 7/8"</i>	T.D. <i>3920'</i>
Csg. <i>8 7/8"</i>	Depth <i>212'</i>
Tbg. Size	Depth
Drill Pipe	Depth
Tool	Depth
Cement Left in Csg.	Shoe Joint
Press Max. <i>200 #</i>	Minimum
Meas Line	Displace
Perf.	

Owner *Same*

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To *Al-La-Lyn Oil Company*
 Street *614 W. 10th*
 City *Ellis*, State *Ks. 67637*

The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No. *Carl McQueen*

CEMENT

EQUIPMENT

No.	Cementor	
Pumptrk <i>191</i>	Helper <i>Gary H. Wayne Mo.</i>	
Pumptrk	Helper	
	Driver <i>Blen C.</i>	
Bulktrk <i>#212</i>		
Bulktrk	Driver	

Amount Ordered	<i>215 sks 60/40 poz 6 bagal with</i>
Consisting of	<i>1/4 # of floeal/sk.</i>
Common	<i>129 sks @ 2.25/sk. \$277.25</i>
Poz. Mix	<i>86 sks @ 2.25/sk. 193.50</i>
Gel.	<i>7 sks @ 6.75/sk. (used 11 sks) 47.25</i>
Chloride	
Quickset	
	<i>Floeal - 54 # @ 1.00/lb 54.00</i>

DEPTH of Job

Reference	Description	Amount
<i>#8</i>	<i>Pumptruck - plug</i>	<i>\$475.00</i>
<i>#13</i>	<i>mileage @ 2.00/mi.</i>	<i>32.00</i>
	<i>1- 8 7/8" dry hole plug</i>	<i>21.00</i>
	Sub Total	\$528.00
	Tax	
	Total	

Handling	<i>@ 1.00/sk (215 sks)</i>	<i>215.00</i>
Mileage	<i>@ 0.44/sk/mi. (16 mi.)</i>	<i>137.60</i>
	Sub Total	\$1324.60
	Total	

Remarks:

1st plug @ 3900' w/25 sks.
2nd plug @ 1800' w/25 sks.
3rd plug @ 1070' w/100 sks.
4th plug @ 260' w/40 sks.
8 7/8" plug @ 40' w/110 sks to surface.

Floating Equipment *Thanks*

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 20 1991
 CONSERVATION DIVISION
 Topeka, Kansas

Plugged rat hole w/15 sks.

ORIGINAL

2627, Russell, Kansas
93-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
Phone Ness City 913-798-3843

NEW

ALLIED CEMENTING CO., INC. N^o 8767

Home Office P. O. Box 31 Russell, Kansas 67665

Date	12-11-90	Sec.	28	Twp.	9	Range	20	Called Out		On Location	1:00 P.M.	Job Start	4:30 P.M.	Finish	5:00 P.M.
Lease	Jackson	Well No. #	1	Location	Pales 1S 17E			County	Rooks	State	KANSAS				
Contractor	Galloway Delg														
Type Job	SURFACE														
Hole Size	12 1/4		T.D.	212											
Csg.	8 5/8		Depth	208											
Tbg. Size															
Drill Pipe															
Tool															
Cement Left in Csg.	10'		Shoe Joint												
Press Max.															
Meas Line															
Perf.															

Owner SAME

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To AI-la-LYN Oil Co.

Street 614 W 10th

City Ellis State Kan 67637

The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No. *[Signature]*

x *[Signature]*

CEMENT

Amount Ordered	140 SKS 60/40		
Consisting of	2% GEL 3% CC		
Common	84	525	441.00
Poz. Mix	56	225	126.00
Gel.	2	6.75	NK
Chloride	4	21.00	84.00
Quickset			

EQUIPMENT

Pumptrk	No.	Cementer	R. DAVIS
	83	Helper	
Pumptrk	No.	Cementer	PAUL
		Helper	
		Driver	
Bulktrk	155		
Bulktrk		Driver	

	Sales Tax	
Handling	1.00	140.00
Mileage 14 mi	.04	78.40
	Sub Total	869.40
	Total	

DEPTH of Job

Reference: # 1		300.00
	1-8 5/8 Plug	42.00
	2.00 PER MILE 14 mi	28.00
	Sub Total	450.00
	Tax	
	Total	

Floating Equipment

Remarks:

CEMENT GR.

RECEIVED
STATE COMMISSION
MAR 20 1991