

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 27 TWP. 9S RGE. 20W E/W
 Location as in quarters or footage from lines:
473' FSL & 802' FWL of NW/4

Lease Owner Kinetic Oil & Gas Exploration, Inc.
 Lease Name Trible Well No. 8
 Office Address 1980 S. Quebec St., Suite 209, Denver, Colorado 80231
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed August 11, 1982
 Application for plugging filed 8-19-82
 Plugging commenced 8-11-82
 Plugging completed 8-11-82
 Reason for abandonment of well or producing formation Dry hole.

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3921'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	301'	8-5/8"	294.83'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

RECEIVED
 STATE CORPORATION COMMISSION
 8/23/82
 AUG 25 1982
 CONSERVATION DIVISION
 Wichita, Kansas


Plugged with 80 sacks cement at 960';
 40 sacks cement at 330'; solid wood bridge
 plug, 1/2 sack hulls, and 10 sacks cement
 at 40'; and 10 sacks cement in rat hole.
 (50-50 Pozmix Cement, 4% Gel, 3% CaCl₂)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John D. Knightley Agent (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
 221 S. Broadway, Wichita, Kansas 67202
 (Address)



SUBSCRIBED AND SWORN TO before me this 19th day of August, 1982

[Signature]
 Notary Public.

My Commission expires: March 12, 1983

15-163-21752-00-00

Kinetic Oil & Gas Exploration, Inc. - Tribble #8
1980 S. Quebec St., Suite 209 473' FSL, 802' FWL
Denver, Colorado 80231 NW/4 Sec. 27-9S-20W
Rooks County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: August 4, 1982
Completed: August 11, 1982

Drillers Log

Clay & Sand	165
Shale	1240
Sand	1460
Red Bed & Shale	1730
Shale	1737
Anhydrite	1787
Shale & Shells	2305
Shale & Lime	2575
Shale & Shells	2820
Shale & Lime	3515
Lime & Shale	3630
Lime	3725
Shale & Lime	3824
Lime	3890
Granite	3892
Lime	3921 RTD

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1982
CONSERVATION DIVISION
Wichita, Kansas