

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME HINKHOUSE

WELL NUMBER 8

SPOT LOCATION SW SW SE

SEC 27 TWP. 9S RGE. 20 ~~XXXX~~ (W)

COUNTY Rooks

Date Well Completed 1949

Plugging Commenced 1/8/87

Plugging Completed 1/8/87

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well TA'd oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist #6 Hays, Kansas

Is ACO-1 filed? N/A if not, is well log attached? yes

Producing formation Arbuckle Depth to top 3867 bottom 3869 T.D. 3880

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3841	3869	8-5/8"	141'	none
				5-1/2"	3840'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Down 3 1/2" at 1250# max. pressure, mixed 40 sks cement & shutin at 1000#

Down annulus (8-5/8" csg) mixed 5 sks cement. Shutin at 1000#

Witness by state pluggger: Dennis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co Inc. License No. _____
Address P.O. Box 31 Russell, Kansas 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

STATE CORPORATION COMMISSION
SUBSCRIBED AND SWORN TO before me this 15 day of January, 19 87
JAN 20 1987

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires: 5/11/87

Mildred Carter
Notary Public

15-163-01740-00-0

WELL LOG

Nadel and Gussman -

Hinkhouse #8

SW SW SE 27-9-20W
Rooks County, Kansas

Date commenced 3-24-49
Date Completed 4-6-49

Casing: 141' 8-5/8"
Cement 100 sax
3840' 5"
Cement 125 sax

Sand and shale	146
Shale	800
Shale and sand	1520
Shale and red bed	1770
Anhydrite	1810
Shale and shells	2270
Shale and lime	2625
Lime	2690
Shale and shells	2825
Lime	2910
Shale and Lime	3449
Shale and Lime	3525
Lime	3790
Conglomerate	3819
Shale and Lime	3839
Arbuckle	3841 T.D.

Elev. 2285 D.F.

T. Lans.	3542
T. Cong.	3787
T. Simpson	3824
T. Arbuckle	3839 D.F.

State of Kansas)

SS:

County of Sedgwick)

Larry C. Hay of lawful age, being first duly sworn on his oath states that the above depths and formations encountered in the above well are correct according to the daily drilling report on said well.

Larry C. Hay

Subscribed and sworn to before me this 14th day of April, 1949

W. C. Bady
Notary Public

My commission expires Nov. 3, 1952

STATE CORPORATION COMMISSION

1/26/87
JAN 20 1987

CONSERVATION DIVISION
Wichita, Kansas