

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01754-00-00

API NUMBER Drilled 06/48

LEASE NAME Rathbun

WELL NUMBER # 2

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 27 TWP. 09 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 06/30/48

Plugging Commenced 08/22/88

Plugging Completed 08/22/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR LASMO Energy Corporation

ADDRESS P.O. Box 1365, Great Bend, Ks. 67530

PHONE# (316) 792-2585 OPERATORS LICENSE NO. 4678

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 11, 1988 (date)

by Shari Feist & District # 4 Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3833 Bottom 3835 T.D. 3835'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	125'	None
				5-1/2"	3834'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pumped down 5-1/2" casing with 90 sacks econolite with 5 sacks hulls.

Maximum Pressure = 1500#. Shut in Pressure = 800#. 5 sacks on backside.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. N/A

Address Box 428, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: LASMO Energy Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Claude Blakesley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Claude Blakesley

(Address) P.O. Box 1365, Great Bend, Ks. 67530



CREATED AND SWORN TO before me this 26th day of August, 19 88

Kathy A. Roberts
Notary Public

My Commission Expires: 3-9-92

Well: Rathbun #2 ^{R.D.}
 Location: SW SW ~~NE~~ Sec. 27-9S-20W, Rocks County, Kansas
 Company: S. A. Murphy
 Contractor: Virginia Drilling Company, Inc.
 Commenced: June 12, 1948
 Completed: June 30, 1948
 Total Depth: 3835
 Elevation: 2283

FORMATION	DEPTH	TOPS:	
Post-Rock-Ft. Hays	0-35	Arbuckle	3633
Shale-sand	35-105	Heebner Shale	3468
Shale-shells	105-125	Lausing-KC	3487
Shale-shells	125-665	Marmaton	3744
Sand	665-890	Socoy Conglomerate	3786
Shells-shale	890-930		
Sand	930-1025		
Sand-shale	1025-1100	CIRCULATE:	
Shale-shells-pyrite	1100-1175	1 hr @ 3623	
Sand	1175-1210	1 hr @ 3632	
Lime-shale	1210-1240	1 1/2 hr @ 3835	
Sand-pyrite	1240-1430		
Shale-shells	1430-1755	Set 2-5/8 @ 125	
Anhydrite	1755-1805	Set 5 1/2" @ 3834	
Shale-shells	1805-2195		
Lime-shale	2195-2235		
Lime-shells-shale	2235-2310		
Lime-shale	2310-2490		
Lime-	2490-2623		
Pyrite	2623-2626		
Lime	2626-2640		
Shale-lime	2640-2685		
Lime	2685-2700		
Lime-shale	2700-3090		
Shale-shells	3090-3110		
Lime-shale	3110-3185		
Lime	3185-3340		
Lime-shale	3340-3352		
Lime	3352-3730		
Lime-shale	3730-3785		
Lime-shale-chert	3785-3814		
Shale-lime	3814-3833		
Dolomite	3833-3835		

RECEIVED
STATE CORPORATION COMMISSION

SEP - 7 1988

CONSERVATION DIVISION
Wichita, Kansas

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and knows of his own knowledge that the Rathbun #2, located in the SW SW ~~NE~~ Section 27-9S-20W, Rocks County, Kansas, was drilled to a total depth of 3835 feet.

R.D.

Subscribed and sworn to before me, a Notary Public, this 12 day of August, 1948.

My commission expires February 5, 1949.