

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-01762-00-00

API NUMBER Spud 1/30/56

LEASE NAME Tribble

WELL NUMBER 7

4950 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 27 TWP. 9 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 2/6/56

Plugging Commenced 10:00 A.M. 1/28/93

Plugging Completed 11:00 A.M. 1/28/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 28, 1993 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3795

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	172'	None
				5 1/2"	3792'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pressured 8 5/8" casing to 500#. Held O.K. Down 5 1/2" casing. Mixed 400# hulls with 260 sx cement. Max Press 1305#. Shut in 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss. \_\_\_\_\_

Dane G. Bales, Manager (Employee of Operator) or (Operator) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 93

BETTY JANE BITTEL  
State of Kansas  
My Appt. Exp. July 17, 1996

Betty Jane Bittel  
Betty Jane Bittel Notary Public

My Commission Expires: July 17, 1996.

RECEIVED  
STATE CORPORATION COMMISSION  
2/11/93  
FEB - 1 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME TRIBLE #7

LOCATION C N/2 NW/4 NW/4 Sec. 27-9S-20W RIG NO. 1

COUNTY ROOKS STATE KANSAS

COMMENCEMENT DATE JANUARY 28, 1956 COMPLETION DATE February 6, 1956

LOG OF WELL

Elevation 2227 rotary bushing. 2224 DF  
 All measurements taken from top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	172	Surface Soil		
172	400	Shale		
400	875	Shale		
375	975	Sand		
975	1210	Shale		
1210	1460	Sand		
1460	1709	Red Bed-Shale		
1709	1748	Anhydrite		
1748	1840	Shale-Shells		
1840	2190	Shale		
2190	2385	Lime-Shale		
2385	2510	Lime-Shale	0° - 2500'	
2510	2615	Lime-Shale		
2615	2745	Lime-Shale		
2745	2895	Lime-Shale	0° - 2750'	
2895	3025	Lime-Shale		
3025	3145	Lime-Shale	0° - 3000'	
3145	3235	Lime-Shale		
3235	3350	Lime-Shale	0° - 3250'	
3350	3415	Lime-Shale		
3415	3518	Lime-Shale	0° - 3500'	
3518	3605	Lime-Shale		
3605	3650	Lime-Shale		
3650	3775	Lime-Shale	0° - 3750'	
3775	3795	Lime-Chert-Shale		DST 3792-95
	3795	TD		

CASING LEFT IN HOLE AFTER COMPLETION

172' of 8-5/8" OD Surface Casing.  
 3799' (118 jts.) of 5-1/2" Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway

Subscribed and sworn to before me this 8th day of February, 1956.

My commission expires:  
 May 20, 1959

Vicky Jacobs  
 Vicky Jacobs, Notary Public  
 RECEIVED STATE CORPORATION COMMISSION  
 FEB - 1 1956  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

RECEIVED  
 FEB 14 1956

n. g. CUMMINGS