

LEASE NAME Rathbun

WELL NUMBER #7

SPOT LOCATION SW-NE

SEC. 27 TWP. 9S RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 8-27-74

Plugging Commenced 3-31-92

Plugging Completed 3-31-92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays District

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing formation Arbuckle Depth to top 3837 bottom 3864.5 T.D. 3844

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil, gas, water	3837	3864	8 5/8	244'	None
				5 1/2	3900'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hooked to 8 5/8"-pumped 1 sx. hulls w/100 sx. 60/40 Poz, 10% gel w/1/4# FloSeal/sx. Max. pressure - 800#. SIP - 400#.  
Hooked to 5 1/2": casing - mixed 5 sxs. hulls w/250 sxs. 60/40 Poz, 10% gel and 1/4# FloSeal/sx. Max pressure - 1200#. SIP - 1000#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. NOTIFIED  
 Address P.O. Box 31, Russell, KS 67665 STATE CORPORATION COMMISSION


4/17/82

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) of  
 (operator) of above-described well, being first duly sworn on oath, says: That  
 I have knowledge of the facts, statements, and matters herein contained and  
 the log of the above-described well as filed that the same are true and  
 correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS



SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1992

Pamela K. Steckel  
 Notary Public

My Commission expires: 11-19-92