

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-00130-00-00

API NUMBER Drilled 5/48

LEASE NAME Tribble

WELL NUMBER 1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 27 TWP. 9 RGE. 20(X) or (W)

COUNTY Rooks

Date Well Completed 5/29/48

Plugging Commenced 6:45 P.M. 2/18/88

Plugging Completed 7:45 P.M. 2/18/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187; Logan, Kansas 67646

PHONE#(913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 18, 1988 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? We have put together log from driller's record. Its all we have.

Producing Formation Arbuckle Depth to Top 3827 Bottom 3834 T.D. 3833

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	180	None
				5 1/2"	3828	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Down 5 1/2" csg. at 700# max. pressure, mixed 4 sx. hulls w/150sx cement and shut in at 300#.

Down annulus (8 5/8" csg.) at 400# max pressure, mixed 1 sx. hulls with 50 sx. cement and shut in at 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Harold Parsons (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold Parsons

(Address) Box 353, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 29 day of February, 19 88



Betty Jane Bittel
Notary Public Betty Jane Bittel

My Commission Expires: July 17, 1988

4/14/88