

LEASE NAME HINKHOUSE

WELL NUMBER 23

2310 Ft. from S Section Line

825 Ft. from E Section Line

SEC. 27 TWP. 9S RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 11-6-76

Plugging Commenced 12-1-94

Plugging Completed 12-1-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Approximately 11/25/94 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3828 Bottom 3889 T.D. 3889

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3828	3889	8-5/8	306'	None
				5-1/2	3886'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforated 2 holes @ 1775 and 1075'. Ran tubing to 3700' and spot 12 sks Gel and 60 sks common cement. Pull tubing to 1775' and circulate to surface with 150 sks cement w/300# hulls. Pull tubing and pump down 5-1/2 w/50 sks cement & 250# hulls. Shut in @ 100 psi. Pump down annulus w/40 sks cement and 100# hulls. Max. 350 psi. Shut-in 250 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. n/a

Address P.O. Box 14, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 94

Kathy Carson
Notary Public

My Commission Expires: 8-1-95

RECEIVED
 STATE CORPORATION COMMISSION
 12/12/94
 DEC 12 1994
 CONSERVATION DIVISION
 WICHITA, KANSAS

DRILLERS' WELL LOG

15-163-20652-0000

DATE COMMENCED: October 29, 1976
DATE COMPLETED: November 6, 1976

Nadel and Gussman
HINKHOUSE # 23
E/2 NW NE SE
Sec 27-T9-R20
Rooks County, Kansas

ELEVATION: 2278 K.B.

0 - 625' Clay and Shale
625 - 1695' Shale and Sand Streaks
1695 - 1764' Shale
1764 - 1802' Anhydrite
1802 - 2033' Shale
2033 - 2428' Shale and Lime
2428 - 3490' Lime and Shale
3490 - 3494' Shale
3494 - 3527' Lime
3527 - 3828' Lime and Shale
3828'-3889' Dolomite
3889' RTD

FORMATION TOPS

Anhydrite 1764
Heebner 3490
Toronto 3509
Lansing 3527
Arbuckle 3828
RTD 3889

SURFACE PIPE:

Set used 8 5/8", 28# pipe
at 306' w/175 sacks Common,
2% Gel, 3% cc.

PRODUCTION PIPE:

Ran used 5 1/2", 14# casing at
3886' w/150 sacks 60/40 Pozmix,
10 bbl flush ahead.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis
RECEIVED
STATE CORPORATION COMMISSION
DEC 1 2 1976

Subscribed and sworn to before me this 8th day of November, 1976.

Wade M. Hoyle
WICHITA, KANSAS
Notary Public

My Commission Expires: April 11, 1978