

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

K.A.R.-82-3-117

15-163-01734-00-00  
API NUMBER N/A

LEASE NAME HINKHOUSE

WELL NUMBER 2

SPOT LOCATION C E/2 E/2 SE <sup>KCC</sup> CAP

SEC. 27 TWP. 9S RGE. 20 ~~XXXX~~ (W)

COUNTY Rooks

Date Well Completed 1948

Plugging Commenced 1/8/87

Plugging Completed 1/8/87

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well TA'd Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist #6 Hays, Kansas

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3839 bottom 3859 T.D. 3859 <sup>3814 KCC CAP</sup> <sub>3844 KCC CAP</sub>

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil	3839	42	8-5/8"	167'	none
		3852	55	5-1/2"	3848	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from     feet to     feet each set.

Down 3 1/2" @ 600# max. pressure, mixed 1 sk hulls w/75 sks cement; shutin at 500#  
down annulus, 8-5/8" csg, at 500# max. pressure, mixed 2 sks hulls w/80 sks cement  
shutin at 300#

Witnessed by state plugger: Dennis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No.             
Address P.O. Box 31 Russell, Kansas 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

STATE CORPORATION COMMISSION

1/20/87  
JAN 20 1987

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) M R Taylor  
3232 First National Tower  
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1987

Mildred Carter  
Notary Public

My Commission expires: 5/11/87

WELL LOG

15-163-01734-00-00

NADEL AND GUSSMAN  
Tulsa, Oklahoma

HINKHOUSE No. 2

C E/2 E/2 27-9-20W  
Rooks County, Kansas

Elevation 2276

CASING  
8-5/8" 167' Cx w/130  
5-1/2" 3844' Sax

Formation	Depth
Surface Clay	70
Shale and shells	730
Shale and shells	900
Sand and shells	1170
Shale and shells	1220
Sand and shells	1412
Shale and shells	1736
Anhydrite and shale	1750
Anhydrite	1785
Shale and Lime	1960
Red beds	1970
Shale and Lime	2156
Shale and shells	2260
Shale and Lime	2475
Lime	2630
Shale and shells	2815
Shale and lime shells	2880
Lime broken	2940
Lime	2957
Shale and lime	3005
Broken Lime	3200
Shale and shells	3283
Lime and shale	3445
Shale and lime broken	3470
Lime	3776
Conglomerate	3780
Chert	3802
Lime and chert	3823
Conglomerate	3841
Lime Arbuckle	3844

~~3844~~

I hereby certify that the above formations and depths are true and correct as taken from the daily drilling reports of the Hinkhouse No. 2 well.

R. C. Hay  
President - Reserve Drilling  
Company, Inc.

Subscribed and sworn to before me this 18th day of June, 1948.

Rola Bask  
Notary Public, in and for  
Sedgwick County, State of Kansas

My commission expires Nov. 3, 1948

JAN 20 1987

CONSERVATION DIVISION  
Wichita, Kansas