

RECEIVED  
4/20/00  
APR 20 2000

CONSERVATION DIVISION  
Wichita, Kansas

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER N/A

LEASE NAME Hinkhouse

WELL NUMBER I

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 27 TWP. 9S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 5/9/48

Plugging Commenced 3/27/00

Plugging Completed 3/27/00

EASE OPERATOR Nadel and Gussman

ADDRESS 15 E. 5th, Suite 3200, Tulsa, OK 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Approximately 3/20/00 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3812 Bottom 3815 T.D. 3815

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Depleted Oil	0	160	8-5/8	160	0
		0	3812	5-1/2	3812	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.

21 gel + 40 sks w/300# hulls @ 3700'. 110 sks w/100# hulls @ 1800'. Cement circulated. Pull tubing and tied on to 5-1/2" and pumped 25 sks @ max psi of 900#. SI @ 300#. Mixed 25 sks and pumped down 8-5/8". Max psi 300#. SI 100#. Total cement used 200 sks.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. N/A

Address P.O. Box 31, Russell, KS 67605


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mr Taylor

(Address) 15 E. 5th, Suite 3200, Tulsa, OK 74103



SUBSCRIBED AND SWORN TO before me this 11th day of April, 2000

Kathy Coarss  
Notary Public

My Commission Expires: 8-1-03

15-163-21733-00-00

WELL LOG

Nadel and Gussman

Hinkhouse No. 1

NE NE SE 27-9S-20W  
Rooks County, Kans.

Commenced 4-23-48  
Completed 5-9-48

160' 8-5/8"  
Cem. 75 sax  
3812 5 1/2"  
CEM 1005AX

Formation

Shale and surface clay	30
Sand	75
Shale and shells	160
Shale and shells	965
Sand and shale	1250
Shale and shells	1780
Shale and Anhydrite	1795
Shale and shells	2250
Shale and Lime	2375
Lime	2500
Shale and Lime	2580
Lime	2592
Shale and lime	2700
Lime, shale and shells	2795
Shale and shells	3025
Shale, Lime and shells	3100
Shale and shells	3390
Lime	3458
Lime	3719
Lime and shale	3760
Shale and chert	3791
Conglomerate	3815. T.D.

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 2000

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above formations and depths are true and correct as taken from the daily drilling reports of the Hinkhouse Well No. 1.

Rola B. Babb  
Secretary - Reserve Drilling Company, Inc.

Subscribed and sworn to before me this 12th day of May, 1948.

My commission expires:

April 26, 1952

B. L. Perry  
Notary Public in and for Sedgwick County, State of Kansas

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: File

DATE <u>3-27-00</u>	SEC. <u>14</u>	TWP. <u>10</u>	RANGE <u>20w</u>	CALLED OUT	ON LOCATION <u>9:15am</u>	JOB START <u>9:30pm</u>	JOB FINISH <u>12:15pm</u>
Hinkhouse LEASE <del>_____</del>		WELL# <u>1</u>	LOCATION <u>Highway 18 &amp; Reel line</u>		COUNTY <u>Roos</u>	STATE <u>Ka</u>	
<input checked="" type="radio"/> OLD <input type="radio"/> NEW (Circle one)				<u>3/4w wite</u>			

CONTRACTOR Express  
TYPE OF JOB Plu

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
CASING SIZE 5 1/2 DEPTH 3700  
TUBING SIZE 2 1/2 DEPTH 3700  
DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
CEMENT LEFT IN CSG. \_\_\_\_\_  
PERFS. \_\_\_\_\_  
DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT  
AMOUNT ORDERED 290 6 3/4 10% gel  
300# hulls  
used 200# 21 gel

COMMON	<u>120</u>	@	<u>6 3/8</u>	<u>762 00</u>
POZMIX	<u>80</u>	@	<u>3 25</u>	<u>260 00</u>
GEL	<u>35</u>	@	<u>9 50</u>	<u>332 50</u>
CHLORIDE		@		
<u>Hulls</u>	<u>3</u>	@	<u>15 50</u>	<u>46 50</u>
		@		
		@		
		@		
		@		
HANDLING		@	<u>1 00</u>	<u>304 00</u>
MILEAGE	<u>4 1/5K</u>	/mile		<u>464 00</u>
				TOTAL <u>2169 50</u>

EQUIPMENT

PUMP TRUCK CEMENTER Mark  
# 345 HELPER Dave  
BULK TRUCK  
# 254 DRIVER Bill  
BULK TRUCK  
# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

SERVICE

21 gel & 40 sy w/300# hulls @ 3700  
110 sy w/100# hulls @ 1800' circ cement  
Came out w/tubing tied onto 5 1/2  
Mixed 25 sy Maypai 900# slid in 300#  
Mixed 25 sy down 8 3/8  
May pai 300# slid in 100#

DEPTH OF JOB	_____		
PUMP TRUCK CHARGE			<u>450 00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>40</u>	@	<u>3 00</u> <u>120 00</u>
PLUG		@	
		@	
		@	
TOTAL <u>570 00</u>			

CHARGE TO: Nadel - Gussman  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

RECEIVED \_\_\_\_\_ @ \_\_\_\_\_  
STATE CORPORATION COMMISSION \_\_\_\_\_ @ \_\_\_\_\_  
**APR 20 2000** \_\_\_\_\_ @ \_\_\_\_\_  
\_\_\_\_\_ @ \_\_\_\_\_

CONSERVATION DIVISION  
Wichita, Kansas

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
TOTAL CHARGE \_\_\_\_\_  
DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Bill Kolo

PRINTED NAME \_\_\_\_\_