

STATE OF KANSAS
STATE CORPORATION COMMISSION
220 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01737-00-00

API NUMBER N/A

LEASE NAME HINKHOUSE

WELL NUMBER 5

SPOT LOCATION C NL N/2 SE

SEC. 27 TWP. 9S RGE 20 ~~XXX~~ (W)

COUNTY Rooks

Date Well Completed 9-6-48

Plugging Commenced 6-17-88

Plugging Completed 6-17-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First Nat'l Tower-Tulsa, OK 74103

PHONE #(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3838 bottom 3839 T.D. 3839'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3838	39	8-5/8"	135'	none
				5-1/2"	3838'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Down 5-1/2" csg @ 800# max press. Mixed 50 sx cement-mixed 4 sx hulls w/115 sx cement and shut in @ 600#. Down annulus (8-5/8") @ 600# max press. Mixed 1 sack of hulls w/110 sx cement and shut in @ 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address P. O. Box 31 Russell, Kansas 67665

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION
6/30/88
JUL 30 1988
(Signature) M R Taylor
Address) 3232 First Nat'l Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 28 day of June, 1988

Mildred Carter
Notary Public

My Commission expires: 5/11/91.

15-163-01737-00-0

WELL LOG

HINKHOUSE No. 5

NADEL AND GUSSMAN
Tulsa, Oklahoma

CNL N/2 SE 27-9-20W
Rooks County, Kansas

Commenced 8-26-48
Completed 9-6-48

135' 8-5/8" cemented 115 sax
3838' 5 1/2" cemented 125 sax

<u>Formation</u>	<u>Depth</u>
Surface	135
Shale, shells and sand	1500
Shale and shells	1765
Anhydrite	1800
Shale and shells	2100
Shale	2305
Shale and lime	3495
Lime	3838
Arbuckle Lime	3839 T.D.

I hereby certify that the above formations and depths are true and correct as taken from the daily drilling reports of the Hinkhouse No. 5 well.

L. C. Hay
President - Reserve Drilling Company

Subscribed and sworn to before me this 29th day of September, 1948.

Nola Babb
Notary Public in and for
Sedgwick County, Kansas.

My commission expires Nov. 3, 1948

RECEIVED
STATE COMMISSION

JUN 30 1988

CONSERVATION DIVISION
Wichita, Kansas