


15-63-19036-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 27 Twp. 9 Rge. 20 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. S. L. SW SW
Lease Owner Nadel and Gussman
Lease Name Hinkhouse Well No. 16
Office Address Box 309, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 8-16 19 50
Application for plugging filed 8-16 19 50
Application for plugging approved 8-16 19 50
Plugging commenced 8-16 19 50
Plugging completed 8-16 19 50
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty
Producing formation Depth to top Bottom Total Depth of Well 3895 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	120	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full heavy mud 3895 to 120 feet - set plug with 25 sacks cement @ 120 feet; then mud to 30' then cement to top of hole

8/28/50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Nadel and Gussman
Address P. O. Box 309, Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Hay (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Hay


(Address)

SUBSCRIBED AND SWORN to before me this 21st day of August, 1950

[Signature]

Notary Public.

My commission expires Nov. 3, 1952



15-163-19036-00-00

WELL LOG

Nadel and Gussman

Hinkhouse No. 16

C SL SW SW 27-9-20W
Rooks County, Kansas

Comm. 8-5-50
Comp. 8-16-50

Casing: 120' 8-5/8"
Cem. w/110 sax.

Elevation 2267'

Shale, Sand and shells	770
Shale shells and sand	1270
Sand	1475
Shale and red bed	1755
Anhydrite	1795
Shale and shells	2355
Shale and lime	2800
Shale and shells	2960
Shale and lime	3035
Shale and shells	3255
Shale and lime	3375
Lime	3440
Shale and lime	3495
Lime	3780
Conglomerate	3805
Chert	3851
Shale	3876
Arbuckle Dolomite	3895

Tops

Heebner Shale	3494
Lansing-Kansas C.	3534
Basal Penn. Shale	3784
Conglomerate	3805
Simpson Shale	3864
Arbuckle	3876

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

L. C. Hay, of lawful age deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of Hinkhouse No. 16 in the Center of the SL SW SW 27-9-20W, Rooks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 21st day of August, 1950.

Notary Public

Notary Public

My commission expires Nov. 3, 1952

PLUGGING
FILE SEC 23 9 20W
BOOK PAGE 27 LINE 15

STATE OF KANSAS

INVOICE

August 18, 1950 194

To: Nadel & Cussman
Box 209
Tulsa, Oklahoma

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: PLUGGING ASSESSMENT AS FOLLOWS:

Hinkhouse Well No. #16
S $\frac{1}{2}$ SW SW 23-9-20W
Rooks County
File No. 22-15

\$25.00

NOTE: We also need a Written Application, a Well Log and a Well Plugging Record on this well to complete our file.

RECEIVED

Conservation Div.

AUG 28 1950

STATE CORPORATION
COMMISSION
KANSAS

17215
Paid
8-28-50
AS L-50

RETURN THIS COPY WITH REMITTANCE

