


15-163-01771-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County, Sec. 32 Twp. 9 Rge. (E) 20 (W)  
Location as "NE/CNW&SW" or footage from lines. SW-NE-SW  
Lease Owner Francis Oil & Gas Inc.  
Lease Name Tucker Well No. 3  
Office Address 905 Palace Bldg. Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 5-16 19 59  
Application for plugging filed 2-6 19 62  
Application for plugging approved 2-6 19 62  
Plugging commenced 2-7 19 62  
Plugging completed 2-7 19 62  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle Depth to top 3844 Bottom 3847 Total Depth of Well 3847 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None
				5 1/2"	3844'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" Circulated W/ Cement.  
5 1/2" 125 sacks behind- DV tool @ 1780' and circulated to 0' W/300 sacks cement no pipe recovery.  
Pumped hole full heavy gel mud (35 sacks), pumped cementing plug, followed by 70 sacks cement, cement 560' to 0'.  
Mudding and cementing by Globe Cementing Co.  
1500# to 1000# standing pump pressure.

3/14/62  
Wichita, Kan.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Francis Oil & Gas Inc and Globe Cementing Co.  
Address Hays, Kansas Plainville, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
I, W.J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 666, Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13 day of March, 19 62

My commission expires  
EVELYN L. MILLER, NOTARY PUBLIC  
Commission Expires Feb. 25, 1963



15-163-01771-00-00

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Francis Oil & Gas, Inc.**

SEC. **32** T. **9** R. **20**  
 LOC. **S4 NE S7 E**

FARM **Tucker**

NO. **3**

TOTAL DEPTH **3847'**

COMM. **5/1/59**

COMP. **5/12/59**


SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED

COUNTY **Rooks**

KANSAS



CASING

20	10	
15	8	202.44 Ft.
12	6	
13	5	3844.50 Ft.

ELEVATION **2264 K.B.**  
**2261 D.F.**  
**2259 O.L.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil & Clay	40'
Sand Stks. & White Clay	120
Shale	210
Shale & Shells	880
Sand	980
Shale, Shells with Sand Stks.	1230
Sand	1510
Red Bed & Shale	1773
Anhydrite	1912
Shale & Shells	2083
Shale & Shells w/Lime Stks.	2140
Shale & Lime	3270
Lime	3358
Shale & Lime	3525
Lime	3570
Kansas City Lime	3626
Lime	3705
Kansas City Lime	3762
Lime Conglomerate	3805
Lime & Shale	3847

Formation Tops:

Topeka	3299	-1035
Reebner	3503	-1239
Toronto	3527	-1263
Lansing	3543	-1279
B. K. C.	3769	-1505
Conglomerate	3820	-1556
Simpson	3835	-1571
Arbuckle	3844	-1580
T. D.	3847	

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

By: *C. L. Spawley*

STATE OF KANSAS  
 SS,  
 COUNTY OF BLANCHARD

Subscribed and sworn to before me, a notary public, in and for said County and State this 14 of May 1959

*Carl Jurey*  
 Notary Public

My Commission Expires Feb. 13, 1960

RECEIVED  
 STATE ENGINEER'S COMMISSION  
 OCT 31 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas