


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

**Rooks** \_\_\_\_\_ County, Sec. 32 Twp. 9 Rge. \_\_\_\_\_ (E) 20 (W)  
Location as "NE/CNW/SW" or footage from lines SW SE NW/4  
Lease Owner Francis Oil & Gas, Inc.  
Lease Name Keller Well No. 1  
Office Address 905 Palace Bldg. Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 3, 1959  
Application for plugging filed September 3, 1959  
Application for plugging approved September 3, 1959  
Plugging commenced September 3, 1959  
Plugging completed September 3, 1959  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3514 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	210	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**FILLED HOLE WITH HEAVY ROTARY MUD to 550 ft.**  
**SET PLUG AND CEMENTED WITH 20 SACKS CEMENT**  
**THROUGH DRILL PIPE. MUDDED TO 180 FT. SET PLUG**  
**AND CEMENTED WITH 15 SACKS CEMENT THROUGH DRILL**  
**PIPE. MUDDED TO 40 FT. SET PLUG AND CEMENTED**  
**WITH 10 SACKS CEMENT AND 1/2 SACK HULLS TO SURFACE.**

**RECEIVED**  
STATE CORPORATION COMMISSION  
9/22/59  
SEP 22 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.  
Address 709 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick,  
L. C. Sponenberg (employee of contractor) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 10th day of September, 1959

My commission expires February 13, 1960

Rose Furey Notary Public.

PLUGGING

File Sec. 32 T 9 R 20W

Book Page 1 Line 43

15-163-19345-00-00

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Francis Oil & Gas, Inc.**  
FARM **Keller** NO. **1**

SEC. **32** T. **9** R. **20**  
LOC. **SW SE NW/4**

TOTAL DEPTH **3514**  
COMM. **8/28** COMP. **9/3/59**  
SHOT OR TREATED  
CONTRACTOR **H-30, Inc.**  
ISSUED

ROCKS  
COUNTY **KANSAS**  


CASING  
20 10  
15 8 **210'**  
12 6  
13 5

ELEVATION **2245 K. B.**  
**2242 D. F.**  
**2240 G. L.**  
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand 30'  
Shale & Shells 210  
Cement 210  
Shale & Shells 785  
Sand 845  
Shale & Shells 1150  
Sand with Shale 1490  
Red Bed 1530  
Red Bed & Shale & Shells 1730  
Anhydrite 1800  
Shale & Shells 2350  
Shale & lime 3505  
Lime 3514

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP 22 1959  
CONSERVATION DIVISION  
Wichita, Kansas

**FORMATION TOPS:**

Topoka 3293 -1048  
Heebner 3504 -1259  
Total depth 3514 -1260

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *L. C. Sponenberg*  
L. C. Sponenberg

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS.

Subscribed and sworn to before me, a Notary Public, in and for said County and State, this 10th day of September, 1959

*Rose Furey*  
Rose Furey, Notary Public

My Commission Expires February 13, 1960.

**PLUGGING**

File Sec. 32 T. 9 R. 20W  
Book Page 1 Line 43