

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 32 Twp. 9 Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner I. O. Miller
Lease Name Hiser Well No. 1
Office Address 619 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed June 8, 1959 19
Application for plugging filed September 4, 1959 19
Application for plugging approved " " " 19
Plugging commenced June 6, 1959 19
Plugging completed " " " 19
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3905' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN

CASING RECORD
RECEIVED
STATE CORPORATION COMMISSION
3/11/63
MAR 11 1963
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" 241' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 450', displaced 20 sax cement through drill pipe at 450', heavy mud to 180', set cementing plug and displaced 20 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Virginia Drilling Co. & Globe Cementing Co.
Address

STATE OF Kansas COUNTY OF Sedgwick, ss.
I. O. Miller (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. O. Miller

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1963

My commission expires June 27, 1965

Notary Public



G. M. HISER #1 - SW SE SE/4 Section 32-9-20 Rocks County, Kansas
 Company - I. O. Miller
 Contractor - Virginia Drig Co Inc.
 Commenced - June 8, 1959
 Completed - June 23rd 1959 - 20th
 Elevation - 2237 RB
 Total Depth - 3905

8 5/8" set at 241 ft. w/ 140 sz con. 2 sz 60
 Dry hole.

FORMATION	DEPTH	GPS:
Surface clay-sand	0- 247	
Shale	241- 665	
Sand	665- 750	
Shale	750- 950	
Sand-shale	950-1040	
Blue Shale-shells	1040-1385	2090 - Ft. Riley
Shale-shells	1385-1725	3496 - Heebner
Anhydrite	1725-1775	3519 - Toronto
Redbed-shale	1775-1865	3537 - Lansing EG
Redbed shale-shells	1865-2105	3760 - Base III
Shale-shells	2105-2305	3819 - Charty Cong.
Shale-lime	2305-2845	3871 - Arbuckle
Lime	2845-3860	3879 - Solid Arbuckle
Conglomerate & lime	3860-3905 F D	

S. A. Murphy
 S. A. Murphy

Subscribed and sworn to before me, a Notary Public,
 this 23rd day of June, 1959.

Wesley H. Austin
 Notary Public

My commission expires: Febr. 5, 1961.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 12 1962
 CONSERVATION DIVISION
 Topeka, Kansas