

LEASE NAME Miller

WELL NUMBER 5

 Ft. from S Section Line

SW SW SE Ft. from E Section Line

SEC. 32 TWP. 9 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 5-28-59

Plugging Commenced 9-27-93

Plugging Completed 9-27-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-27-93 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	203	8 5/8		None
	Casing	0	3799	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same, and depth placed, from feet to feet each set.
Perf. 1970 and 800'. Ran tubing to 3600' spot 50 sk. 60/40 pos, 10% gel and 200# hulls. Pull up to 2500' and spot 50 sk. 60/40 pos, 10% gel 200# hulls. Pull up to 1700' and spot 50 sk. 60/40 posmix, 10% gel. Pull up to 800'. Mix 60 sk. 60/40 pos, 10% gel and 200# hulls. Cement circulate to surface. Pull tubing. Squeeze in 25 sk. 60/40 pos, 10% gel, 300# max. 100# SIP.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact: statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Kansas 67601



AND SWORN TO before me this 6 day of October, 19 93

Rosemary Smith
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas
 10/8/93

My Commission Expires: 5-1-1995

USE ONLY ONE SIDE OF EACH FORM