


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

GRAHAM

County. Sec. 12 Twp. 9 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW SE

Lease Owner DANE G HANSEN EST

Lease Name EICHMAN #8

Well No.

Office Address Box 187, LOGAN, KANSAS 67646

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 4/27/67 19

Application for plugging filed 4/27/67 19

Application for plugging approved 4/27/67 19

Plugging commenced 9:00 PM 4/27/67 19

Plugging completed 4/27/67 19

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, MORELAND, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 3690' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	178.27	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 540'. SET PLUG. PUT IN 20 SACKS CEMENT and 1/2 SACK HULLS. FILLED WITH HEAVY MUD to 160'. SET PLUG. PUT IN 20 SACKS CEMENT AND 1/2 SACK HULLS. FILLED WITH HEAVY MUD TO 40'. SET PLUG. FILLED TO TOP WITH 10 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
5/8/67  
MAY 8 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C-G DRILLING CO.  
Address 107 RULE BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. G F GALLOWAY

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. GALLOWAY

107 RULE BUILDING (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of MAY, 1967

My commission expires JAN. 23, 1968

PHYLLIS McJIMSEY Notary Public.

W E L L    L O G

OPERATOR: DANE G. HANSEN EST  
 WELL NAME: EICHMAN #8                      LOCATION: NE SW SE SEC 12-9-21W  
 COUNTY: GRAHAM COUNTY                      STATE: KANSAS  
 WELL COMMENCED: 4/18/67                      WELL COMPLETED: 4/27/67  
 ELEVATION: 2136 KB                      TOTAL DEPTH: 3690'  
 PRODUCTION: DRY & ABANDONED                      RIG NO: 2  
 CASING - 8-5/8": 178.27 (9 jts) W/130 sx cement + 2 sx ca. cl.  
 5-1/2": \_\_\_\_\_

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
178	1120	SHALE	1/4° 500'	
1120	1350	SAND	3/4° 1000'	
1350	1400	SHALE	1° 1500'	
1400	1629	RED BED SHALE	1-3/4° 2000'	
1629	1672	ANHYDRITE	1-3/4° 2165'	
1672	1750	RED BED & SHALE	1-1/2° 2280'	
1750	2225	SHALE & SHELLS	2° 2460'	
2225	3470	LIME & SHALE	1-1/4° 2555'	DST #1 3442-3470'
3550	3670	LIME	1-1/2° 2710'	DST #2 3667-3670'
3675	3690	ARBUCKLE		MISSRUN DST #3 3667-3675'
				DST #4 3642-3681'

MAY 8 1967  
 DIVISION

STATE OF KANSAS  
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, This 2nd day of MAY, 1967.

My comm. exp: Jan. 23, 1968

Phyllis McJimsey  
 Phyllis McJimsey ---Notary Public