

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: R & B Oil & Gas, Inc.  
Address: 111 N. Blaine, Attica, KS 67009  
Phone: (620) 254-7294 Operator License #: 31191  
Type of Well: Gas - OIL PKT Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Doug Louis (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Miss Depth to Top: 4594 Bottom: 4608 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-20196-00-00  
Lease Name: Hughbanks - Miller Gas Unit  
Well Number: 1-12 KCC PKT 4/13/07  
Spot Location (QQQQ): C - W/2 - NE - NE  
660 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 12 Twp. 34 S. R. 9  East  West  
County: Harper  
Date Well Completed: Spud: 6-3-73  
Plugging Commenced: 3-7-07  
Plugging Completed: 3-9-07

Show depth and thickness of all water, oil and gas formations.


| Oil, Gas or Water Records |           | Casing Record (Surface Conductor & Production) |      |       |        |            |
|---------------------------|-----------|--|------|-------|--------|------------|
| Formation                 | Content   | From   | To   | Size  | Put In | Pulled Out |
| Mississippi               | Oil & Gas | 4594   | 4608 |       |        |            |
|                           |           |  |      | 8 5/8 | 269    |            |
|                           |           |  |      | 4 1/2 | 4594   | 2890       |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Sand at 4540', bailed 4 sacks cement, dug cellar, set floor, pulled slips, had 25" stretch, cut surface off 4' below ground, ripped casing at 3060', worked pipe, ripped casing at 2890', came free, pulled casing up to 1400', pumped 35 sacks at 1400', pulled to 850', pumped 35 sacks, pulled to 320', circulated with 100 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 401 W. Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: R & B Oil & Gas Inc.  
State of KANSAS County, HARPER, ss.

R & B Oil & Gas, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Randy Newberry, President  
(Address) PO Box 195, Attica, KS 67009  
SUBSCRIBED and SWORN TO before me this 9th day of April, 2007  
Jane Swingle My Commission Expires: 1-6-2011  
Notary Public, Jane Swingle

