


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

T - 9 NORTH R - 20W



Locate well correctly on above Section Plat

Rooks County, Sec. 20 Twp. 9 Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines NW NE N2W NE KCC
Lease Owner Frank J Black
Lease Name Neil Well No. 3
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 1-19 19 52
Application for plugging filed 12-30 19 60
Application for plugging approved 1-3 19 61
Plugging commenced 1-3 19 61
Plugging completed 3-21 19 61
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3844 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	145'	None
				5 1/2	3838'	884'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3830' - dumped 4 sks cement - pulled pipe to 550' - pumped in 20 sks mud and 20 sks cement - pulled pipe to 150' - pumped in 20 sks cement - finished pulling casing - mudded to 30' - set 10' rock bridge - dumped in 10 sks cement

RECEIVED
STATE CORPORATION COMMISSION
5/11/61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box #572, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF MCPHERSON, ss.
Frank J. Black (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
(Address) _____

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1961

My commission expires July 16, 1963
JERRY PELTZMAN Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East M. Ardock, Wichita, Kansas


15-163-03537-00-00
COPY

Company- VIRGINIA DRILLING COMPANY, INC. et al
Farm- Neil No. 3

SEC. 20 T. 9 R. 20W
~~NW NE NE~~
N2N2NE KCL
ZAP

Total Depth. 3844
Comm. 1-5-52 Comp. 1-19-52
Shot or Treated.
Contractor. Virginia Drlg Co., Inc.
Issued. 5-24-52

County Rocks
KANSAS



CASING:
8 5/8" 145'
5 1/2" 3838'

Elevation. 2271 DF

Production. 27 bbls / 4% water

Figures indicate Bottom of Formations

clay, shale	33
clay, sand	85
shale	270
shale, shells	620
sand, shale	1145
shale, sandstone	1448
shale, shells	1600
shale, shells, redbed	1765
anhydrite	1805
shale, shells	2200
lime, shale	2495
shale	2585
lime	2665
lime, shale	2786
shale	2950
lime, shale	3271
lime	3501
lime, shale	3541
lime	3790
shale	3804
lime, shale	3840
lime	3844
Total Depth	

Tops:	
Heebner	3504
Toronto	3528
Lansing KC	3545
Base KC	3764
Conglomerate	3814
Simpson	3826
Arbuckle	3836

RECEIVED
STATE GEOLOGICAL COMMISSION
JAN 3 1961
CORRELATION DIVISION
Wichita, Kansas