

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,966 -00-02

LEASE NAME Smith B swd

WELL NUMBER 1

2310 Ft. from S/N Line of Section (circle one)

2310 Ft. from E/W Line of Section (circle one)

SPOT LOCATION - NW - NW - SE

SEC. 11 TWP. 9 S. RGE 20 (E) or (W)

COUNTY Rooks

Date Well Completed 10/12/79

Date Plugging Commenced 9/5/96

Date Plugging Completed 9/5/96

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE OPERATOR Thomason Petroleum Inc.

ADDRESS Box 875

CITY, STATE, ZIP Hays, Kansas 67601

PHONE#(913) 6259045 OPERATORS LICENSE NO. 9957

Character of Well disposal well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/5/96 (date)

by Dennis Hammel (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? Was sent with CP 1

Producing Formation(s) L/KC Depth to Top 3361 Bottom 3542 T.D. 3708

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Toronto	lime	3342	3362	8 5/8"	209	none
L/KC	lime	3362	3581	4 1/2"	3708	none

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran 2 3/8" tubing to 1450' mixed 75 sks 60/40 pos 10% gel w/300 lbs. hulls, Pumped down tubing until it circulated, Pull tubing & mixed 110 sks of same with 200 hulls, down casing Shut in Psi. 500 lbs. 8 5/8" full of cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Stewart well service

License No. 31720

Address 2511 E. 21st. Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thomason Petroleum Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Steven Thomason (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 875 Hays, Kansas 67601



SUBSCRIBED AND SWORN TO before me this 25th day of September, 1996

Donald D. Schuster
Notary Public

My Commission Expires: July 30, 1999