

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: White Hawk Oil Company
Address: P. O. Box 1150
Phone: (620) 792-4309 Operator License #: 5163
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: August, 2006 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Chat Depth to Top: 2756' Bottom: 2770' T.D. 2770'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 113-01968 -- 00 - 00
Lease Name: Frisbie
Well Number: #1
Spot Location (QQQQ): _____ - SE - SE - NW
2310 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 6 Twp. 18 S. R. 1 East West
County: McPherson
Date Well Completed: 08/19/47
Plugging Commenced: April 2, 2007
Plugging Completed: April 4, 2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Chat	Depleted			8-5/8"	144'	0
				5-1/2"	2756'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Scott's Well Service, Inc. MIRU. Pulled rods & pump. Rigged for tubing & pulled tubing. Sanded bottom off to 2720'. Dumped 5 sks 60/40 Poz, 4% gel on bottom. Cut surface pipe off & took slips out of casing. Built bridge in casing @ 450'. Filled casing to surface with cement. Ran 1" pipe to 300' & cemented to surface. Pulled 1" pipe, tore down. Total cement used 170 sks., 40/60 Poz., 4% gel. On 4/09/2007 McPherson Concrete used 11 sks cement to top off. Greg Eves and Virgil Clothier on location for KCC.

Name of Plugging Contractor: Scott's Well Service, Inc. License #: 6819

Address: P. O. Box 136, Roxbury, Kansas 67476

Name of Party Responsible for Plugging Fees: White Hawk Oil Company, P. O. Box 1150, Great Bend, Kansas

State of Kansas County, Barton, ss.


Rebecca Dunlap (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rebecca Dunlap
(Address) P.O. Box 1150 Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 10th day of May, 20 07
M. Lynne Wooster My Commission Expires: 4-2-11
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION
Mail to: KCC - Conservation Division, 100 S. Market - Room 2078, Wichita, Kansas 67202

MAY 11 2007
CONSERVATION DIVISION
WICHITA, KS



[Handwritten signature]