

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: KNIGHTON OIL COMPANY  
Address: 221 S. Broadway, Suite 710 Wichita, Kansas 67202  
Phone: (316) 264-7918 Operator License #: 5010  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: May 7, 2007 (Date)  
by: Patrick Staab (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
See Attached Sheet Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-NA 065-01913-00-00  
Lease Name: East Elrick  
Well Number: 1-1  
Spot Location (QQQQ): C - SW - NW - NW  
990 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 11 Twp. 10 S. R. 25  East  West  
County: Graham  
Date Well Completed: 8/12/1960  
Plugging Commenced: 5/7/2007  
Plugging Completed: 5/7/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	170'	8 5/8"	170'	None
Lansing	oil and water	Surface	4205'	5 1/2"	3980'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2" tubing to 2711', spot 150 sacks cement with 400# hulls, pulled up to 2010' and circulated cement to surface with 40 sacks and 200# hulls.  
Came out with tubing, hooked to casing with 5 1/2" swage and pumped in another 20 sacks. 8 5/8" backside squeezed with 10 sacks

Name of Plugging Contractor: Express Well Service License #: 6426  
Address: P.O. Box 19 Victoria, KS 67671

Name of Party Responsible for Plugging Fees: Knighton Oil Company, Inc.

State of Kansas County, Sedgwick, ss.

Earl M. Knighton, Jr (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.  
(Address) 221 S. Broadway, Suite 710 Wichita, KS 67202

**DAVID D. MONTAGUE**  
Notary Public - State of Kansas  
My Appt. Expires 10-4-07

SWORN TO before me this 14th day of May, 20 07  
David D. Montague Notary Public My Commission Expires: 10-4-07

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 14 2007  
CONSERVATION DIVISION  
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKA

Attachment

Knighton Oil Company, Inc.  
East Elrick #1-1

Perforations in Lansing Formation:

3744-50, 3791-98, 3818-21, 3825-29, 3887-91, 3908-17, 3928-31, 3950-53, RBP 3960'

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 14 2007

CONSERVATION DIVISION  
WICHITA, KS

Allied Cementing Co., LLC  
 24 S. Lincoln  
 P.O. Box 31  
 Russell, KS 67665

\*\*\*\*\*  
 \* I N V O I C E \*  
 \*\*\*\*\*

Invoice Number: 108645

Invoice Date: 05/10/07

Sold Knighton Oil Co., Inc.  
 To: 710 Petroleum Bldg.  
 221 S. Broadway  
 Wichita, KS  
 67202

Cust I.D.....: Knig  
 P.O. Number...: E. Elrick 1-1  
 P.O. Date.....: 05/10/07

Due Date.: 06/09/07  
 Terms....: Net 30

Salesperson...:

Item I.D./Desc.	Ordered	Unit	Price	Net	TX
Common	132.00	SKS	11.1000	1465.20	T
Pozmix	88.00	SKS	6.2000	545.60	T
Gel	19.00	SKS	16.6500	316.35	T
Hulls	6.00	SKS	25.5000	153.00	T
Handling	435.00	SKS	1.9000	826.50	T
Mileage	84.00	MILE	39.1500	3288.60	T
435 sks @.09 per sk per mi					
Plug	1.00	JOB	955.0000	955.00	T
Mileage pmp trk	84.00	MILE	6.0000	504.00	T

All Prices Are Net, Payable 30 Days Following  
 Date of Invoice. 1 1/2% Charged Thereafter.  
 If Account CURRENT take Discount of 805.42  
 ONLY if paid within 30 days from Invoice Date

Subtotal:	8054.25
Tax.....:	447.02
Payments:	0.00
Total....:	8501.27

*PLUGGING  
 CEMENT (#1)*

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 MAY 14 2007  
 CONSERVATION DIVISION  
 WICHITA, KS

**WELL FILE**

# ALLIED CEMENTING CO., INC.

32957

EMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>5-7-07</u>	SEC. <u>11</u>	TWP. <u>10s</u>	RANGE <u>25w</u>	CALLED OUT	ON LOCATION	JOB START <u>12:01 PM</u>	JOB FINISH <u>1:00 PM</u>
LEASE <u>EAST ERIE</u>	WELL # <u>1-1</u>	LOCATION <u>ST. PETER IN 1/4 E 1/4 S.</u>		COUNTY <u>GRAHAM</u>	STATE <u>KANSAS</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Express Well Service

TYPE OF JOB Plug Abandoned well

HOLE SIZE 7 7/8 T.D. 4205'

CASING SIZE 5 1/2 DEPTH 3980'

TUBING SIZE 2" DEPTH 2766'

~~DRILL PIPE~~ 8 3/4 Surface DEPTH 170'

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS. 3960 PBTB

DISPLACEMENT

OWNER

CEMENT (USED 220 SK.)

AMOUNT ORDERED 400 SK 60% 10% GEL

600 # Hull's

COMMON	<u>132 SK</u>	@ <u>11.10</u>	<u>1465.20</u>
POZMIX	<u>88 SK</u>	@ <u>6.20</u>	<u>545.60</u>
GEL	<u>19 SK</u>	@ <u>16.65</u>	<u>316.35</u>
CHLORIDE		@	
ASC		@	
Hull's	<u>6 SK</u>	@ <u>25.50</u>	<u>153.00</u>
		@	
		@	
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>435</u>	@ <u>1.90</u>	<u>826.50</u>
MILEAGE	<u>84</u>	@ <u>.09</u>	<u>3288.60</u>
TOTAL SK			<u>6595.25</u>

EQUIPMENT

PUMP TRUCK CEMENTER GIRAN

# 398 HELPER GARY

BULK TRUCK

# 396 DRIVER JOHN

BULK TRUCK

# DRIVER

REMARKS:

Ran 2" Tubing to 2711' - Spot 150 SK Cement w/ 400 # Hull's, Pulled up to 2010' & Circulated Cement to Surface w/ 40 SK & 200 # Hull's. Came out w/ Tubing, Hooked to CSG w/ 5 1/2 Swage & Squeezed in another 20 SK. 8 3/4 Bore pipe squeezed in 10 SK & shot in. THANK'S

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>955.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>84</u>	@ <u>6.00</u>	<u>504.00</u>
MANIFOLD	@	
	@	
	@	

CHARGE TO: KNIGHTON Oil Co.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

# 7163.69

AFTER DISCOUNT,

BEFORE SALES TAX.

TOTAL 1459.00

PLUG & FLOAT EQUIPMENT

RECEIVED @ \_\_\_\_\_

KANSAS CORPORATION COMMISSION @ \_\_\_\_\_

MAY 14 2007 @ \_\_\_\_\_

CONSERVATION DIVISION @ \_\_\_\_\_

WICHITA, KS

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Kenneth Werner

Kenneth Werner Mr.

PRINTED NAME

WELL FILE