

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: R. J. Enterprises  
Address: 1203 East 4th Avenue, Garnett, KS 66032  
Phone: (785 ) 448 -6995 448-7725 Operator License #: 3728  
Type of Well: Injection Docket #: E-03098  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No  
Producing Formation(s): List All (If needed attach another sheet)  
Squirrel Depth to Top: 820 Bottom: 860 T.D. 860  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 003-19056 -00 -00  
Lease Name: Ware  
Well Number: 11-G  
Spot Location (QQQQ): ApSW - NE - SW - NE  
3355 Feet from ☐ North / ☒ South Section Line  
1925 Feet from ☒ East / ☐ West Section Line  
Sec. 15 Twp. 21 S. R. 20 ☒ East ☐ West  
County: Anderson  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: September 7, 2006  
Plugging Completed: September 7, 2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Squirrel	Surface			10-3/4"	13'	0
	Production			4-1/2"	820'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tried to pull packer and 2" and couldn't with pulling unit. Moved in drilling rig. Hooked onto 2" and packer and could move 2" - 4' or 5'

but couldn't get it to come. Pulled up tight and backed off 2" pipe. Pulled 450' of 2". Ran 1" in and tried to get back

inside of 2" and couldn't. Pumped 24 sacks cement at 450'. Pulled out and hooked on to 4-1/2" and squeezed 36 sacks cement.

Total of 60 sacks cement. The 4-1/2" cemented to surface with 293 sacks cement.

Name of Plugging Contractor: R. J. Enterprises License #: 3728

Address: 1203 East 4th Avenue, Garnett, KS 66032

Name of Party Responsible for Plugging Fees: Roger Kent

State of Kansas County, Anderson, ss.

Roger Kent  
(Employee of Operator) or (Operator) on above-described well, being first duly  
sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the  
same are true and correct, so help me God.


(Signature) Roger Kent

(Address) 1203 East 4th Avenue, Garnett, KS 66032

SUBSCRIBED and SWORN TO before me this 15th day of May, 20 07

Donna Manda  
Notary Public

My Commission Expires: March 16, 2011



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

KANSAS CORPORATION COMMISSION

MAY 18 2007

CONSERVATION DIVISION  
WICHITA, KS