

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEREXCO, INC.

Address: PO BOX 723 HAYS, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4-30-07 (Date)

by: CASE MORRIS (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

L-KC Depth to Top: 3034 Bottom: 3066 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-03268-00-00

Lease Name: NWBU NW Beaver Unit

Well Number: T4-W1 KCCPFT 6/6/07

Spot Location (QQQQ): SE - NE - NE - per CP-2/3
4290 Feet from ☐ North / ☒ South Section Line

330 Feet from ☒ East / ☐ West Section Line

Sec. 6 Twp. 16 S. R. 12 ☐ East ☒ West

County: BARTON

Date Well Completed: 1-17-48

Plugging Commenced: 4-30-07

Plugging Completed: 4-30-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
L-KC	OIL	0	3200	5-1/2' 14#	1-17-48	----
		0	526	8-5/8	1-17-48	----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

DIG OUT CELLAR POORBOY 8-5/8 TO 5-1/2, RIG UP, RUN TBG AND CATCHER TO 3000' RELEASE AND PULL LOCKSET RIG UP
PERF TECH SHOOT 2 HOLES AT 1590-750-575 RUN OPEN ENDED TBG TO 3016. RIG UP ALLIED CEMENTING PUMP
100 SKS 60/40 POS 10% GEL 300# HULLS, PULL TO 1599 PUMP 120 SKS 200# HULLS CIRC CMT TO SURFACE. PULL TBG
HOOK TO 5-1/2 PUMP 70 SKS 100# HULLS CIRC CMT TO SURFACE ON 8-5/8. SHUT 8-5/8 IN PUMP 10 SKS MAX PRESSURE 500# SHUT IN 200#

Name of Plugging Contractor: STEWART WELL SERVICE Berexco Inc License #: 4604 5363

Address: 1409 WASHINGTON CIRCLE HAYS, KS 67601

Name of Party Responsible for Plugging Fees: ROBERT GRANT W/ BEREXCO, INC.

State of KS County, ELLIS, ss.

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Robert Grant
(Address) PO BOX 723 HAYS, KS 67601

SUBSCRIBED and SWORN TO before me this 11 day of MAY, 20 07

Shanna Miller
Notary Public

My Commission Expires: 9/19/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202