

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 015-21795 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: Bear Petroleum, Inc. KCC License #: 4419  
(Owner / Company Name) (Operator's)

Address: P.O. Box 438 City: Haysville

State: KS Zip Code: 67060 Contact Phone: ( 316 ) 524 - 1225

Lease: Anderson Well #: 1 Sec. 34 Twp. 25 S. R. 5  East  West

NE - SE - SW Spot Location / QQQQ County: Butler

990 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2970 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 207' Cemented with: 100 Sacks

Production Casing Size: 4 1/2" Set at: 2588' Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2528-34', 2539-44'

Elevation: 1341 ( G.L. /  K.B.) T.D.: 2588 PBDT: 2570 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): According to the rules and regulations of the KCC

**RECEIVED**  
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

**MAY 14 2007**

If not explain why? \_\_\_\_\_ CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dick Schremmer

Bear Petroleum, Inc. Phone: ( 316 ) 524 - 1225

Address: P.O. Box 438 City / State: Haysville, KS 67060

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529

(Company Name) (Contractor's)

Address: P.O. Box 467, Chase, KS 67524-0467 Phone: ( 620 ) 938 - 2943

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-11-07 Authorized Operator / Agent: \_\_\_\_\_  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NO LOG

HAROLD D AND ON REPLACEMENT CARD: 34-25-5E  
 1001 TOWANDA AVE #1 ANDERSON NE SE SW  
 EL DORADO, KS 67042  
 CONTR EDCO DRILLING CO CTY BUTLER  
 GEOL DEAN SEEBER FIELD EL DORADO  
 E 1346 KB CM 7/15/81 CARD ISSUED 12/31/81 IP P 14 BOPD & 40 % W  
 1341 GL HUNT 2528-34

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ADM		662	+ 684
B/ADM		676	+ 670
LANS		1731	- 385
BONN SPR		1860	- 514
KC		2024	- 678
B/KC		2184	- 838
MARM		2258	- 912
CHER		2390	-1044
ARD		2458	-1112
HUNT		2528	-1182
VIOLA		2544	-1198
SIMP		2564	-1218
PBTD		2570	-1224
RTD		2588	-1242

8-5/8" 207/100sx, 4 1/2" 2588/75sx  
 NO DST'S  
 MICT - CO, PF (HUNT) 7/2528-34, SWB  
 DWN, NO FL, AC 250G, SWB LD & REC 7  
 BOPH & 2 BWPH/2.5 HRS, ONFU 300' FL,  
 SWB DWN & SWB DRY, AC 1000G (15%), SWB  
 150 FL (90% O) EVERY 6"/3 HRS, POP,  
 P 50 BO & 5 BWPD, 8/16/81, DECL &  
 STAB AT 14 BOPD & 40% WTR, 12/31/81

INFO RELEASED: 2/4/82 WAS TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 MAY 14 2007  
 CONSERVATION DIVISION  
 WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   Robert E. Krehbiel, Commissioner   Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Bear Petroleum, Inc.  
PO Box 438  
Haysville, KS 67060

May 15, 2007

Re: ANDERSON #1  
API 15-015-21795-00-00  
NESESW 34-25S-5E, 990 FSL 2970 FEL  
BUTLER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000

Sincerely

Barry Metz  
Deputy Director