

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 007-23138-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 4-17-2007

Well Operator: Shelby Resources, LLC KCC License #: 31725

Address: P.O. Box 1213 (Owner / Company Name) City: Hays (Operator's)

State: Kansas Zip Code: 67601 Contact Phone: ( 785 ) 623 - 3290

Lease: Thompson Trust Well #: 3-17 Sec. 17 Twp. 31 S. R. 14  East  West

- approx. - NW - NW Spot Location / QQQQ County: Barber

641' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

463' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 20" Set at: 52' Cemented with: 10 Sacks

Surface Casing Size: 8-5/8" Set at: 1134' Cemented with: 430 Sacks

Production Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

List (ALL) Perforations and Bridgeplug Sets: \_\_\_\_\_

Elevation: 1659 ( G.L. /  K.B.) T.D.: 4570' PBTD: 4568' Anhydrite Depth: \_\_\_\_\_ (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Mix heavy mud in the hole. Mix 50 sxs. of cement @1160'. Mix 40 sxs. @ 260' and the top plug @ 60' with 20 sxs. Make sure cement comes to surface. Plug rathole with 15 sxs. and mousehole with 10 sxs. All plugs were with 60/40 poz with 6% gel.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? ACO-1 will be sent in the next 30 days.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Shelby Resources, LLC  
(Brian Karlin) Phone: ( 785 ) 623 - 3290

Address: P.O. Box 1213 City / State: Hays, Kansas 67601

Plugging Contractor: Allied Cementing Company, Inc. KCC License #: \_\_\_\_\_  
(Company Name) (Contractor's)

Address: P.O. Box 368, Medicine Lodge, Kansas 67104-0368 Phone: ( 620 ) 886 - 5926

Proposed Date and Hour of Plugging (if known?): 4-30-2007 4-29-07 - 10:30 AM

RECEIVED

KANSAS CORPORATION COMMISSION

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-07-2007 Authorized Operator / Agent: Brian Karlin (Signature)

MAY 29 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 CONSERVATION DIVISION WICHITA, KS

*\* Well already plugged - KCC-DIG*

*DIST 01*