

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22704-00-00  
Spot: NENENE Sec/Twnshp/Rge: 27-11S-16W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BOWLBY Well #: 1  
County: ELLIS Total Vertical Depth: 3400 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 4.5   | 3355       | 0           | 200 SX  |
| SURF   | 8.625 | 400        | 0           | 200 SX  |

\$ 110.50

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2007 12:00 PM  
Plug Co. License No.: 33669 Plug Co. Name: WESTERN WELL DRILLING, LLC  
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2007 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RIH with tubing to 2016' - pumped 100 sxs cement with 400# hulls.  
Pulled tubing to 999' - pumped 120 sxs cement with 200# hulls.  
Pulled tubing to 340' - pumped 55 sxs cement with 100# hulls.  
Ran out of cement - ordered 250 sxs more cement.  
Pulled tubing out - waited on cement.  
RIH with tubing to 317' - pumped 60 sxs cement with 100# hulls - circulated cement.  
Pulled tubing - tied on to 5 1/2" - squeezed 50 sxs cement.  
S.I.P. 800#.  
Tied onto backside - pumped 50 cement full to the top.

Perfs:

**INVOICED**  
DATE 5-18-07  
INV. NO. 2007061765

Remarks: ALLIED CEMENTING COMPANY-TICKET #22054.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

MAY 16 2007

CONSERVATION DIVISION  
WICHITA, KS

MAY 14 2007

REPLACEMENT CARD


TEXOKKA DRILLING INC.  
2705 VINE, #8  
HAYS, KS. 67601

#1 BOWLBY

27-11-16W  
NE NE NE

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOLOGICAL \_\_\_\_\_ FIELD CHRISLER EAST EXT  
(1/8 S)



ELV 1737 KB SPD E11/25/81 <sup>CARD</sup> ISSUED 8/12/82 IP P 11 BOPD & WTR  
MARM - INTV NA

API 15-051-22,704

| LOG      | Tops ..... | Depth/Datum |
|----------|------------|-------------|
| ANH      | 886+       | 851         |
| TOP      | 2653-      | 916         |
| HEEB     | 2898-      | 1161        |
| TOR      | 2918-      | 1181        |
| LANS     | 2947-      | 1210        |
| BKC      | 3172-      | 1435        |
| MARM LM  | 3201-      | 1464        |
| MARM CHT | 3254-      | 1517        |
| ARB      | 3330-      | 1593        |
| RTD      | 3500-      | 1763        |

E 8 5/8 " 400, PROD CSG NA  
NO CORES OR DSTS  
MCT - CO, PF (MARM) INTV NA, SWB DWN, SO, PF (KC) INTV  
NA, SWB DWN, SO, POP, P 11 BOPD & WTR - NO OTHER INFO  
TO BE RELEASED BY OPERATOR

INFO RELEASED: 10/30/86 - ADDED WELL INFO