

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20774-00-00  
Spot: S2S2 Sec/Twnshp/Rge: 28-12S-34W  
650 feet from S Section Line, 2620 feet from W Section Line  
Lease Name: FRAHM UNIT Well #: 1  
County: LOGAN Total Vertical Depth: 4720 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	241		

\$ 153.40

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2007 4:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: GREG UNRUH Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 05/10/2007 6:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2550' w/25 sxs.  
2nd. Plug at 1575' w/100 sxs.  
3rd. Plug at 300' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:


INVOICED  
DATE 5-21-07  
INV. NO. 2007061775

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

MAY 14 2007

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-23  
MAY 16 2007  
CONSERVATION DIVISION  
WICHITA, KS