

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06878-00-00  
Spot: NWSW Sec/Twnshp/Rge: 15-14S-14W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: HORACE FINK Well #: 2  
County: RUSSELL Total Vertical Depth: 3125 feet

Operator License No.: 5147  
Op Name: BEREDCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	5.5	2996		w/355 sxs cmt
PROD	7	3024	0	w/unknown sxs cmt
SURF	10.75	180	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2007 12:00 PM  
Plug Co. License No.: 5147 Plug Co. Name: BEREDCO, INC.  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 455 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2007 3:20 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RIH with tubing to 2949' - pumped 125 sxs cement w/500# hulls.  
Pulled tubing to 1808' - pumped 100 sxs cement.  
Pulled tubing to 887' - pumped 110 sxs cement with 100# hulls.  
Pulled tubing out - tied onto 7" - squeezed with 80 sxs cement.  
S.I.P. 100#.  
Tied onto backside - pumped 60 sxs cement - filled up 10" to top.  
Plug complete.

Perfs:

Top	Bot	Thru	Comments
3122	3125		GOH
3110	3118		F
3102	3105		E
3068	3076		C
3044	3060		B
3028	3039		A
2927	2934		PLATTS
2918	2922		PLATTS
750	900		250 SXS
473	675		400SXS


**INVOICED**  
DATE 5-18-07  
INV. NO. 2007061766

Remarks: ALLIED CEMENTING COMPANY-TICKET #22056.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

MAY 16 2007

CONSERVATION DIVISION  
WICHITA, KS

MAY 14 2007

