

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-24050-00-00
Spot: NWNESW Sec/Twnshp/Rge: 3-24S-13E
2280 feet from S Section Line, 1620 feet from W Section Line
Lease Name: STAUFFER L Well #: 3-B3
County: GREENWOOD Total Vertical Depth: 2162 feet

Operator License No.: 32912
Op Name: CARROLL ENERGY, LLC
Address: 200 ARCO PLACE, STE 230 PO BOX 14
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	2160	2160	
SURF	8.625	44		12 SX CMT. \$ 70.27

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/16/2007 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 2160', 50' cement plug @ 500', 275' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2007 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2160' pumped 15 sxs cement. Pulled tubing to 500' pumped 15 sxs cement, pulled tubing to 275' pumped 90 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 14 2007 MH

CHANUTE, KS

INVOICED
DATE 5-21-07
INV. NO. 2007061768

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

MAY 17 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

ID# 48-1214033
 AC ID# 156212
 Shop # 620 437-2661
 Cellular # 620 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5926
 Shop Address: 3613A Y Road
 Madison, KS 66860

Hurricane Truck Services, Inc.
P.O. Box 782228
Wichita, KS 67278-2228

Cement and Acid
Service Ticket
T 1797

DATE 3-16-07

COUNTY Greenwood CITY _____

CHARGE TO Carroll Energy, LLC
 ADDRESS 2198 Valley High Dr. CITY Independence ST Ks ZIP 67301
 LEASE & WELL NO. Stauffer #3-B3 CONTRACTOR Hurricane Well Serv
 KIND OF JOB Plug To Abandon SEC. _____ TWP. _____ RNG. _____
 DIR. TO LOC. _____ OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
120	SKS 60/40 Pozmix cement		600.00
410	lbs GEL 4%		889.20
			73.80
300	lbs GEL - Spacer between Plugs		54.00
4	Hrs Water Truck		300.00
	BULK CHARGE		
5.36	TRK MILES - minimum charge		200.00
20	PUMP TRK. MILES		55.00
1	2 7/8" Float Shoe (Use on Plugging Wells)		84.00
	PLUGS		
		6.9% SALES TAX	69.36
		TOTAL	2325.36

T.D. 2160 CSG. SET AT _____ VOLUME _____
 SIZE HOLE 6 3/4" TBG SET AT _____ VOLUME _____
 MAX. PRESS. _____ SIZE PIPE _____
 PLUG DEPTH _____ PKER DEPTH _____
 PLUG USED _____ TIME FINISHED 12:45 pm

REMARKS: Set Cement Plugs as follows:
15 SKS @ 2160
15 SKS @ 500
90 SKS @ 275 To Surface
120 SKS Total

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 17 2007
 CONSERVATION DIVISION
 WICHITA, KS

EQUIPMENT USED

NAME Don Kimbrell UNIT NO. 185 NAME Brandon #91 UNIT NO. James #23
Brad Butler CEMENTER OR TREATER called by Bert Loventz OWNER'S REP.