

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00848-00-00
Spot: SWNESE Sec/Twnshp/Rge: 26-12S-22W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 6-3
County: TREGO Total Vertical Depth: 4030 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4030	0	w/175 sxs cmt
SURF	8.625	515	0	w/300 sxs cmt

\$ 130.98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2007 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JAY PORTER Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered out 475 sxs 60/40 pozmix - 10% gel - 800# hulls.
Squeeze jobs: Nov. 1954 - 1180' w/150 sxs; June 1976 - 1160'-1180' w/755 sxs.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2007 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 4000'. Copeland pumped 110 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 2500' - pumped 110 sxs cement with 300# hulls.
Pulled tubing to 1100' - pumped 90 sxs cement with 200# hulls - circulated cement.
PTOH. Squeezed casing with 10 sxs.
Max. P.S.I. 300#. S.I. P. 300#.
Hooked up to backside and pumped 90 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

INVOICED

DATE 5-21-07
INV. NO. 200 706177

Remarks: LEASE ORIGINALLY KNOWN AS SCOTT CHAS #3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Richard Williams

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

MAY 16 2007

CONSERVATION DIVISION
WICHITA, KS

MAY 11 2007

TEXAS COMPANY

#3

SCOTT

26-12-22W

SW NE SE

Contr.

TREGO

County

E 2350

Comm.

Comp.

11-23-51

IP

3000 BOPD (ARB)

DRAW DOWN

Tops	Depth	Datum
TOP	3377	-1027
HEEB	3576	-1226
LANS	3608	-1258
ARB	3992	-1612
T.D.	4030	-1680

Casing

8" 515 PERF 31 S, 3995-4005
 5" 4030 3 BOPH: PB 4029:
 ACID 500:
 PERF 78 S, 4005-28:
 SWB 60 BOPH

OGALLAH POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS