

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20799-00-01
Spot: NWNW Sec/Twnshp/Rge: 17-33S-43W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: TURMORROW MORROW UNIT Well #: 401W
County: MORTON Total Vertical Depth: 5330 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		4664		STUCK IN HOLE
PROD	4.5	5015	2340	WITH 150 SX CMT
SURF	8.625	1417		WITH 700 SX CMT

\$ 173.23

Well Type: EOR UIC Docket No: E27951.2 Date/Time to Plug: 04/12/2007 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2007 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PACKER STUCK IN HOLE @ 4664'. SINKER BAR STUCK IN HOLE AT 3800'. PUMP 100# HULLS WITH 20 SX CMT THROUGH TUBING TO PLUG PERFS. PUMP 200# HULLS WITH 20 SX CMT THROUGH TUBING AT TOP OF FISH @ 3600' INSIDE 4 1/2" CASING. PLUG AT 1430' WITH 50 SX CMT. PLUG AT 660' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4715	4734		

INVOICED
DATE 5-31-07
INV. NO. 2007061804

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Jim Holland PJT/II
(TECHNICIAN) RECEIVED

KANSAS CORPORATION COMMISSION

MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3