

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25638-00-00
Spot: NENWSW Sec/Twnshp/Rge: 22-14S-16W
2310 feet from S Section Line, 1260 feet from W Section Line
Lease Name: DREILING C Well #: 6
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 4787
Op Name: DENNING, TOM DBA T. D. I. OIL OPER
Address: 1310 BISON RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

113.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/04/2007 5:15 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: ELDO Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Order 125 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 05/04/2007 7:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3340' w/25 sxs.
2nd. Plug at 1000' w/25 sxs.
3rd. Plug at 425' w/50 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED
DATE 5-21-07
INV. NO. 2007061778

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

MAY 16 2007

CONSERVATION DIVISION
WICHITA, KS

MAY 14 2007

