

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10043-00-00
Spot: SW Sec/Twnshp/Rge: 31-32S-42W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: HANKE Well #: 1-31
County: MORTON Total Vertical Depth: 3318 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E. 5TH, SUITE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3314	820	TOC 2125
SURF	8.625	595		WITH 400 SX CMT \$107.84

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/26/2007 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN MAY Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: TUBING TO 2500' WITH 600#HULLS & 25 SX CMT. PULL CASING. PLUG AT 1400'+/- OR STUB 50 SX CMT AT 625'. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2007 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 500# HULLS & 25 SX CMT AT 1950'. PLUG AT 650' WITH 80 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3258	3264		
3232	3238		
3220	3224		
3193	3214		
3168	3180		
3129	3131		
3114	3117		
3047	3068		
3039	3043		
3031	3037		
2990	2995		
2978	2980		
2966	2971		
2901	2905		
2872	2880		
2836	2838		
2790	2794		
2734	2743		
2696	2698		
2678	2684		

INVOICED
DATE 5/31/07
INV. NO. 2007061800

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

James D Holland
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP 23

Handwritten initials