

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21531-00-00
Spot: SESENE Sec/Twnshp/Rge: 8-23S-33W
2440 feet from N Section Line, 115 feet from E Section Line
Lease Name: ARTHUR MAYER SWD Well #: 1
County: FINNEY Total Vertical Depth: 1630 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	1524	0	WITH 240 SX CMT
SURF	4.5	1091	0	WITH 240 SX CMT

\$ 52.98

Well Type: SWD UIC Docket No: D27414.0 Date/Time to Plug: 04/25/2007 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: FILL 2 3/8" FIBERGLASS TUBING WITH CMT WITH HULLS TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2007 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 2 3/8" FIBERGLASS CASING WITH 48 SX CMT & 60# HULLS FROM 1524' TO 0'.
PRESSURE TO 300#. LOAD 2 3/8" X 4 1/2" ANNULUS WITH 3 SX CMT AND
PRESSURED TO 200#. TUBING & ANNULUS STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
1478	1630		
1460	1524		

INVOICED


DATE 5-23-07

INV. NO. 200 7061786

Remarks: USED CLASS CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP 2/3

MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS