

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02811-00-00 ⁰² *KC 08*
Spot: S2SWNE Sec/Twnshp/Rge: 9-9S-23W *5-29-07*
2970 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BRUSH CREEK UNIT Well #: 304
County: GRAHAM Total Vertical Depth: 3910 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| PROD | 5.5 | 3910 | 0 | w/125 sxs cmt |
| SURF | 8.625 | 223 | 0 | w/175 sxs cmt |

\$127.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2006 9:00 AM
Plug Co. License No.: 33555 Plug Co. Name: K C WELL SERVICE, INC.
Proposal Rcvd. from: RON NELSON Company: DARRAH, JOHN JAY, JR. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugged thru tubing. Squeezed casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/31/2006 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:
RIH with tubing to 3600' - pumped 2 sxs cement and 8 sxs gel.
Pulled up to 2577' with 8 sxs gel.
Pulled up to 1554' - pumped 260 sxs cement - lost circulation.
Pulled up to 777' - pumped 125 sxs cement - good circulation.
Pulled all tubing - tied onto casing and squeezed 25 sxs cement.
S.I.P. 400#.

Perfs: **INVOICED**
8-4-06
DATE 20070603
TIME 3:15
KCC WICHITA
RECEIVED
AUG 03 2006
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS BEIKER B-4. COPELAND CEMENT COMPANY-TICKET #30604.
Plugged through: TBG

District: 04 Signed *Marvin Mills*
HO (TECHNICIAN)

IMPERIAL OIL OF KANS

#1

BEIKER 'B'

9-9-23W

S2 SW NE

Contr. IMPERIAL OIL OF KANS

GRAHAM

County

E. 2388RB Comm.

Comp. 11-29-57

IP 153 BOPD/LANS

PERM PMP

| Tops | Depth | Datum |
|------|-------|-------|
| | | |
| HEER | 3666 | -1278 |
| TOR | 3687 | -1299 |
| LANS | 3698 | -1310 |
| | | |
| | | |
| | | |
| | | |
| | | |
| TD | 3910 | -1522 |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 223

5" 3910

DST 3721-34/2 HR, 800' G, 180'

MDY 0, BHP 1225#

DST 3736-43/2 HR, G/45", 3620'

0, BHP 1330#

CO 3900: PERF 28/3886-90: ACID

250: SWB 7 BOPH/12 HR, NW: 28/

3866-70: PKR 3860: ACID 3000

BRUSH CREEK POOL ACID 2500:

SWB 22 BOPH/

8 HRS, 600'

OB

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |
| + | + | + |

11-29-57