

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20255-00-00
Spot: W2E2SW Sec/Twnshp/Rge: 3-23S-33W
1320 feet from S Section Line, 1700 feet from W Section Line
Lease Name: J J MEYER GAS UNIT Well #: 2
County: FINNEY Total Vertical Depth: 2638 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2450		WITH 2 SX CMT
PROD	5.5	2638	0	WITH 750 SX CMT
SURF	8.625	371		WITH 275 SX CMT

\$ 85.74

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/25/2007 12:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: SET CIBP @ 2450' WITH 2 SX CMT. FILL 5 1/2" CASING WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2007 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

HOLES IN CASING FROM 1066-1088'. CIBP @ 2450' WITH 2 SX CMT. PUMP 125 SX CMT & 75# HULLS DOWN 5 1/2" CASING. FILL FROM 1088' TO 0'. PRESSURED TO 400# & HELD. HOOK UP TO 5 1/2" X 8 5/8" ANNULUS AND FILL WITH 7 SX CMT. PRESSURED TO 250# & HELD. TOP OFF 5 1/2" CASING WITH 2 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2503	2582		

INVOICED
DATE 5-23-07
INV. NO. 2007061786

Remarks: USED CLASS C CMT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form 2/3

MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS