

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20269-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 14-15S-9E
3198 feet from S Section Line, 566 feet from E Section Line
Lease Name: JOHNSON Well #: 1
County: WABAUNSEE Total Vertical Depth: 3380 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	304		

\$ 109.85

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/16/2007 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Revd. from: RON GULICK Company: GULICK DRILLING, COMPANY, IN Phone: (620) 583-3066

Proposed Plugging Method: 50' PLUG AT THE SIMPSON, 50' PLUG AT THE HUNTON, 50' PLUG AT THE MISSISSIPPI, 50' PLUG AT THE KANSAS CITY, 100' PLUG AT 354', CEMENT FROM 60' TO SURFACE, 15 SACKS IN RATHOLE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 03/16/2007 12:30 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN TUBING TO 3280' AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 2959' AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 2540' AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 1800' AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 354' AND PUMPED 35 SACKS OF CEMENT. PULLED THE TUBING UP TO 60' AND PUMPED 25 SACKS OF CEMENT. FILLED THE RATHOLE WITH 15 SACKS OF CEMENT.

Perfs:

INVOICED
DATE 6-5-07
INV. NO. 2007061828

RECEIVED
KCC DISTRICT #3

MAY 18 2007 TCH

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

MAY 25 2007 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

PH