

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20687-00-00
Spot: N2S2NW Sec/Twnshp/Rge: 13-1S-35W
3630 feet from S Section Line, 3960 feet from E Section Line
Lease Name: CHADDERDON Well #: 4
County: RAWLINS Total Vertical Depth: 4318 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4317	0	w/510 sxs cmt
SURF	8.625	314	0	w/185 sxs cmt

\$ 140.34

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2007 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered 300 sxs of SMD cement and 500# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2007 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 314' w/185 sxs cement.
4 1/2" production casing set at 4317' w/510 sxs cement.
TD 4318'. PBT 4285'. BP set at 4181'. Casing had holes.
Ran tubing to 3100' - pumped 50 sxs cement with 300# hulls.
Pulled tubing to 2100' - pumped 50 sxs cement with 100# hulls.
Pulled tubing to 1100' - pumped 30 sxs cement with 50# hulls - cement to surface.
Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4101	4104		
4066	4068		
4047	4049		

INVOICED

DATE 6-5-07
INV. NO. 2007061829

Remarks: SWIFT SERVICES CEMENT-TICKET #11892.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 29 2007

MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS

PD

BURCH EXPLORATION, INC
PARKER, CO 80134

13-01 -35W
C N/2 S/2 NW

#4 CHADDERDEN

site: 10-3/4 N & 8-1/4 W OF ATWOOD, KS

city: RAWLINS


API 15-153-20687

contr: GOLDEN EAGLE DRILLING INC

field: CAHOJ WEST

geol: PAUL PRIJATEL

fr date 06/16/87 spd data 07/01/87 drig comp 07/11/87 card issued 01/27/88 last revised 01/27/88



elv: 3126 KB LOG
tops.....depth/datum
SC.....3018 +108
TOP.....3855 -729
DR CR.....3900 -774
OREAD.....3952 -826
LANS A.....4046 -920
LANS B.....4102 -976
LANS C.....4149 -1023
LANS D.....4201 -1075
LANS E.....4240 -1114
LANS F.....4302 -1176
BKC.....4353 -1227
PBTD.....4285 -1159
RTD.....4318 -1192

IP status:
OIL, P 5 BO & 115 BWPD, LKC 4202-4243 OA,
CSG: 8-5/8" 314 / 185 SX, 4-1/2" 4317 / 510 SX
NO CORES
DST (1) 4130-4170 (LANS C), / 15-30-25-0, NB, REC 60'
M ISIP 200# IFP 57# -57# FFP 66# -66# IHP 1998#
FHP 1995# BHT 126 *

(over)

DST (2) 4228-4265 (LANS E), / 15-30-90-90, REC 60' OIL SPTD M, 60' SLI OC SPTD MW, 120'
W, W / FEW OIL SPKS, 180' W ISIP 324# FSIP 324# IFP 85# -104# FFP 133# -209# IHP
2103# FHP 2103# BHT 132 *
MICT - CO, PF (LANS E) 4240-4243, W / 4 SPF, AC 500 GAL (15% MCA), SWB DWN, SO, PF
(LANS D) 4202-4205, W / 4 SPF, AC 500 GAL (15% MCA), SWB DWN, SO, SET 2-3/8" TBG AT
4284, POP, P 5 BO & 115 BWPD, 8/1/87